



Rocky Flats Environmental Technology Site

PRE-DEMOLITION SURVEY REPORT (PDSR)

BUILDING 910 CLOSURE PROJECT

REVISION 0

November 15, 2002



**CLASSIFICATION REVIEW NOT REQUIRED PER
EXEMPTION NUMBER CEX-005-02**

ADMIN RECORD

IA-A-001180

1/91

PRE-DEMOLITION SURVEY REPORT (PDSR)

BUILDING 910 CLOSURE PROJECT

REVISION 0

November 15, 2002

Reviewed by:

Don Ruck for Paul Miles Date: 11-19-02
Paul Miles, Quality Assurance

Reviewed by:

D.P. Snyder Date: 11-19-02
D.P. Snyder, RISS ESH&Q Manager

Approved by:

Karen Wiemelt Date: 11-19-02
Karen Wiemelt, K-H Project Manager

2

9 REFERENCES

- DOE/RFFO, CDPHE, EPA, 1996. Rocky Flats Cleanup Agreement (RFCA), July 19, 1996.
- DOE Order 5400.5, "Radiation Protection of the Public and the Environment."
- DOE Order 414.1A, "Quality Assurance."
- EPA, 1994. "The Data Quality Objective Process," EPA QA/G-4.
- K-H, 1999. Decommissioning Program Plan, June 21, 1999.
- MAN-131-QAPM, *Kaiser-Hill Team Quality Assurance Program*, Rev. 1, November 1, 2001.
- MAN-076-FDPM, *Facility Disposition Program Manual*, Rev. 3, January 1, 2002.
- MAN-077-DDCP, *Decontamination and Decommissioning Characterization Protocol*, Rev. 4, July 15, 2002.
- MAN-127-PDSP, *Pre-Demolition Survey Plan for D&D Facilities*, Rev. 1, July 15, 2002.
- MARSSIM - Multi-Agency Radiation Survey and Site Investigation Manual (NUREG-1575, EPA 402-R-97-016).
- PRO-475-RSP-16.01, *Radiological Survey/Sampling Package Design, Preparation, Control, Implementation, and Closure*, Rev. 1, May 22, 2001.
- PRO-476-RSP-16.02, *Pre-Demolition (Final Status) Radiological Surveys of Surfaces and Structures*, Rev. 1, May 22, 2001.
- PRO-477-RSP-16.03, *Radiological Samples of Building Media*, Rev. 1, May 22, 2001.
- PRO-478-RSP-16.04, *Radiological Survey/Sample Data Analysis for Final Status Survey*, Rev. 1, May 22, 2001.
- PRO-479-RSP-16.05, *Radiological Survey/Sample Quality Control for Final Status Survey*, Rev. 1, May 22, 2001.
- PRO-563-ACPR, Asbestos Characterization Procedure, Revision 0, August 24, 1999.
- PRO-536-BCPR, Beryllium Characterization Procedure, Revision 0, August 24, 1999.
- RFETS, Environmental Waste Compliance Guidance #25, Management of Polychlorinated Biphenyls (PCBs) in Paint and Other Bulk Product Waste During Facility Disposition.
- RFETS, Environmental Waste Compliance Guidance #27, Lead-Based Paint (LBP) and Lead-Based Paint Debris Disposal.
- RFETS, RFCA RSOP for Recycling Concrete, September 28, 1999
- Reconnaissance Level Characterization Report for Group A Facilities, October 14, 1999, Revision 0.

8 FACILITY CLASSIFICATION AND CONCLUSIONS

Based on the analysis of radiological, chemical and physical hazards, Building 910 is classified as an RFCA Type 2 facility pursuant to the RFETS Decommissioning Program Plan (DPP; K-H, 1999). PDS results indicated that no radiological or chemical contamination exists in excess of the PDSP unrestricted release limits except for two sand-filter tanks in the basement of B910. The sand-filter tanks have been drained of liquids, are radiologically clean on the outside but contain very low levels of residual transuranic and uranium contamination on the inside. The two sand-filter tanks were sealed and will be removed and packaged as radioactive waste during the demolition of the building. PCB ballast and hazardous waste items have been removed and disposed of in compliance with Environmental Protection Agency (EPA) and Colorado Department of Public Health and Environment (CDPHE) regulations.

The PDS for Building 910 was performed in accordance with the DDCP and PDSP, all PDSP DQOs were met, and all data satisfied the PDSP DQA criteria. Environmental media beneath and surrounding the facilities will be addressed at a future date in accordance with the Soil Disturbance Permit process and in compliance with RFCA. To ensure that Building 910 remains free of contamination and that PDS data remain valid, isolation controls have been established, and the facilities are posted accordingly.

12

6 DATA QUALITY ASSESSMENT

Data used in making management decisions for decommissioning of Building 910, and consequent waste management, are of adequate quality to support the decisions documented in this report. The data presented in this report (Attachments B and C) were verified and validated relative to DOE quality requirements, applicable EPA guidance, and original project DQOs.

In summary, the Verification and Validation (V&V) process corroborates that the following elements of the characterization process are adequate:

- ◆ the *number* of samples and surveys;
- ◆ the *types* of samples and surveys;
- ◆ the sampling/survey process as implemented "in the field"; and
- ◆ the laboratory analytical process, relative to accuracy and precision considerations.

Details of the DQA are provided in Attachment D.

7 DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES

The demolition and disposal of Building 910 will generate a variety of wastes. Estimated waste types and waste volumes are presented below. All wastes can be disposed of as sanitary waste, except PCB Bulk Product Waste and the two sand filter tanks. PCB ballast and hazardous waste items have been removed and managed pursuant to Site PCB and waste management procedures. All concrete surfaces can be used as backfill onsite in accordance with the RFCA RSOP for Recycling Concrete.

WASTE TYPES AND VOLUME ESTIMATES							
Facility	Concrete (cu ft)	Wood (cu ft)	Metal (cu ft)	Corrugated Sheet Metal (cu ft)	Wall Board (cu ft)	ACM (cu ft)	Other Waste (cu ft)
910	15,000	0	4.0	8.0	0	100	None

Note: Approximately 400 cubic feet of low level waste will be generated during the disposal of the two radiologically contaminated sand-filter tanks that will be removed during demolition.

4.3 RCRA/CERCLA Constituents [including metals and volatile organic compounds (VOCs)]

Building 910 was initially proposed as a RCRA Unit. However, the RCRA permit was never established and RCRA wastes were not introduced into the facility. During component removal activities, samples were taken from the sand filters and analyzed for RCRA metals. The results of these samples did not indicate the presence of any RCRA contaminants. The results of these samples are included in Attachment C, Chemical Data Summaries and Sample Maps - Metals Case Narrative for Kaiser Hill, RIN02S0203. Additionally, a significant amount of paint from the basement floor has peeled due to frequent groundwater infiltration. The D&D contractor's Industrial Hygiene personnel performed field sampling of the paint using an XRF machine and determined that the paint did not contain lead. A visual inspection of the empty building by RISS Environmental Compliance personnel verified the absence of hazardous waste stains and/or residuals on the walls, interior surface of the roof and concrete pad. Therefore, RCRA/CERCLA contamination is not a concern, and samples were not taken as part of this PDS.

The building may have contained some RCRA regulated items, such as mercury thermostats, fluorescent light bulbs, mercury vapor light bulbs, mercury containing gauges, circuit boards, and lead-acid batteries. However, these items have been removed and are being managed in accordance with the Colorado Hazardous Waste Act.

4.4 Polychlorinated Biphenyls (PCBs)

Based on the HSAR for the Group A facilities, interviews, facility walkdowns and a review of historical WSRIC processes, Building 910 does not have a history of PCB use or storage. The facility may have contained PCB fluorescent light ballast, however, all PCB ballast have been removed from the facility and will not impact decontamination and decommissioning activities.

Based on the age of B910, paints used on the facility may contain PCBs; and therefore, painted surfaces will be managed as PCB Bulk Product Waste. Painted concrete surfaces can be used as backfill on site in accordance with approval received from EPA in November 2001 (letter from K. Clough, US EPA Region 8, to J. Legare, DOE RFFO, 8EPR-F, Approval of the Risk-Based Approach for Polychlorinated Biphenyls (PCB)-Based Painted Concrete).

5 PHYSICAL HAZARDS

Physical hazards associated with Building 910 consists of those common to standard industrial environments, and include hazards associated with energized systems, utilities, and trips and falls. Building 910 contains a full-length basement plus an additional six foot deep (approximate) sump pit located in the southeast corner of the basement. Two sand filter tanks located in the basement will be removed as low-level radioactive waste during demolition. There is a chemical sump pit located on the eastside of Building 910 that is approximately eight feet deep. There are no other unique hazards associated with the facility. The facility has been relatively well maintained and is in good physical condition, and therefore, does not present hazards associated with building deterioration. Physical hazards are controlled by the Site Occupational Safety and Industrial Hygiene Program, which is based on OSHA regulations, DOE orders, and standard industry practices.

10

4 CHEMICAL CHARACTERIZATION AND HAZARDS

Building 910 was characterized for chemical hazards per the PDSP. Chemical characterization was performed to determine the nature and extent of chemical contamination that may be present on, or in the facility. Based upon a review of historical and process knowledge, visual inspections, and PDSP DQOs, additional sampling needs were determined. A Chemical Characterization Plan was developed during the planning phase that describes sampling requirements and the justification for the sample locations and estimated sample numbers. The contaminants of concern were asbestos and beryllium. Refer to Attachment C, Chemical Summary Data and Sample Maps, for details on sample results and sample locations. Isolation control postings are displayed on affected structures to ensure no hazardous materials are introduced.

4.1 Asbestos

A survey of building materials suspected of containing asbestos was conducted in Building 910 in accordance with the RLC for Group A facilities dated October 14, 1999 (Refer to RF/RMRS-97-035, *Asbestos and Lead Characterization Report, Building 910 and Tank 215-D* in the Group A project files). A CDPHE-certified asbestos inspector conducted the inspections, and suspect materials were identified for sampling at the discretion of the inspector. Asbestos containing material identified during the RLC was the vapor barrier mastic coating on the thermal systems insulation (5% to 8% Chrysotile). This friable asbestos containing TSI will be removed prior to demolition. As part of the PDS, additional asbestos sampling was performed on the interior cinderblock walls, which had not been sampled during the RLC. All PDS bulk asbestos samples were "None Detected." The PDS asbestos laboratory sample data and location maps are contained in Attachment C, Chemical Data Summaries and Sample Maps. The RLCR asbestos sampling data are contained in the Group A RISS characterization project files.

4.2 Beryllium (Be)

A beryllium survey was conducted in Building 910 as part of the Group A RLCR dated October 14, 1999. For the RLCR, limited biased sampling was performed in Building 910. Three (3) beryllium smear samples were taken and all results were less than the investigative limit of $0.1 \mu\text{g}/100\text{cm}^2$. On this basis, 20 biased beryllium smear samples were taken as part of this PDS. The beryllium smear samples for the PDS were collected in accordance with the PDSP and the *Beryllium Characterization Procedure*, PRO-536-BCPR, Revision 0, September 9, 1999.

All beryllium smear sample results from Building 910 taken during the PDS and the RLC were less than the investigative limit of $0.1 \mu\text{g}/100\text{cm}^2$. PDS beryllium laboratory sample data and location maps are contained in Attachment C, Chemical Data Summaries and Sample Maps. The RLCR beryllium sampling data are contained in the Group A RISS characterization project files.

9

B910 Interior (Survey Unit 910-A-002)

The interior was classified as a MARSSIM Class 3 Survey Unit. Prior to the PDS, a process waste line that passed through the north wall of B910 basement was removed. Also, piping associated with two sand filters located in the east end of the basement was removed. The two sand filters were sealed and will be removed and packaged as radioactive waste during the demolition of the building. The sand-filter tanks have been drained of liquids, are radiologically clean on the outside and contain very low levels of residual transuranic and uranium contamination on the inside (2.284 pCi/gram total activity). Remaining tanks and equipment were released through the Property Waste Release Evaluation (PWRE) process. All equipment and tank PWRE survey results (including both interior and exterior surfaces) were less than the applicable DCGL values; PWRE surveys are included in Attachment B, Radiological Data Summary and Survey Maps.

A total of 33 TSA measurements (16 random grid, and 15 biased and 2 QC) and 31 RSA measurements (16 random grid and 15 biased) were taken and scan surveys performed. Alpha scan surveys of 5% of interior surfaces (155 m² minimum) at biased locations were performed. None of the measurements or scans indicated elevated activity above applicable DCGL values. Radiological survey data, statistical analysis results, survey locations, and radiological scan maps are presented in Attachment B, Radiological Data Summary and Survey Maps.

B910 Exterior (Survey Unit 910-B-001)

The B910 exterior was classified as a MARSSIM Class 2 Survey Unit. A total of 32 TSA measurements (15 random, 15 biased, and 2 QC) and 30 RSA measurements (15 random and 15 biased) were taken. Alpha scan surveys of 100% of the north wall (167 m² minimum) and 50% of the remaining exterior surfaces (764 m² minimum) at biased locations were performed. None of the measurements or scans indicated elevated activity above applicable DCGL values. Soil inside the Drying Beds (228A and 228B) east of B910 was evaluated for potential contaminants. Based on process history, past operational use (i.e., no process liquids discharged in to the basins), and surrounding soil levels, the soil inside the Drying Beds was determined to be characteristic of surrounding soils outside the Drying Beds (i.e., less than Tier II levels). Thus, the Drying Bed concrete is acceptable for demolition and disposal as clean material or onsite recycle material. The exterior surfaces of B910 are acceptable for unrestricted release. Refer to Attachment B, Radiological Data Summary and Survey Maps, for survey data, statistical analysis results, survey locations and radiological scan maps.

8

2 HISTORICAL SITE ASSESSMENT

A Facility-specific Historical Site Assessment (HSA) and Reconnaissance Level Characterization (RLC) was conducted to understand the facility history and related hazards. The HSA consisted of facility walkdowns, interviews, and document review, including review of the Historical Release Report, and were used to design the RLC. The Building 910 RLC was performed in FY 1999 as part of the Group A Facilities' RLCR (Refer to *Reconnaissance Level Characterization Report for Group A Facilities*, dated October 14, 1999, Rev. 0). Based on the RLC results, B910 was classified as a Type 2 facility, and therefore, PDS characterization was required before demolition of the facility. This report documents the results of that PDS. The HSA and RLC results were used to identify PDS data gaps and needs, and to develop radiological and chemical PDS characterization packages. HSA and RLC documentation are located in the RISS Characterization Project files.

3 RADIOLOGICAL CHARACTERIZATION AND HAZARDS

Building 910 was characterized for radiological hazards per the PDSP. Radiological characterization was performed to define the nature and extent of radioactive materials that may be present on the facility surfaces. Measurements were performed to evaluate the contaminants of concern. Based upon a review of historical and process knowledge, building walk-downs, and MARSSIM guidance, a Radiological Characterization Plan was developed during the planning phase that describes the minimum survey requirements (refer to the RISS Characterization Project files for the Building 910 Radiological Characterization Plan). Two radiological survey unit packages were developed: 910-A-002 for B910 interior and 910-B-001 for B910 exterior. Individual radiological survey unit packages are maintained in the RISS Characterization Project files.

Building 910 survey unit packages were developed in accordance with Radiological Safety Practices (RSP) 16.01, *Radiological Survey/Sampling Package Design, Preparation, Control, Implementation and Closure*. Total surface activity (TSA), removable surface activity (RSA), and scan measurements were collected in accordance with RSP 16.02 *Radiological Surveys of Surfaces and Structures*. Radiological survey data were verified, validated and evaluated in accordance with RSP 16.04, *Radiological Survey/Sample Data Analysis*. Quality control measures were implemented relative to the survey process in accordance with RSP 16.05, *Radiological Survey/Sample Quality Control*. Radiological survey data, statistical analysis results, survey locations, and radiological scan maps are presented in Attachment B, Radiological Data Summary and Survey Maps.

1 INTRODUCTION

A Pre-Demolition Survey (PDS) was performed to enable compliant disposition and waste management of Building 910. Because this Type 2 building will be demolished, the characterization was performed in accordance with the Pre-Demolition Survey Plan (MAN-127-PDSP). Building surfaces characterized as a part of this PDS included walls, ceilings and roofs. Environmental media beneath and surrounding the facilities were not within the scope of this PDS and will be addressed in accordance with the Soil Disturbance Permit process and in compliance with RFCA.

As part of the Rocky Flats Environmental Technology Site (RFETS) Closure Project, numerous facilities will be removed. Among these is Building 910. The location of this facility is shown in Attachment A, Facility Location Map. This facility no longer supports the RFETS mission and will be removed to reduce Site infrastructure, risks and/or operating costs.

Before this Type 2 facility can be demolished, the Data Quality Objectives (DQOs) for a Pre-Demolition Survey (PDS) must be satisfied; this document presents the PDS results for Building 910. The PDS was conducted pursuant to the Decontamination and Decommissioning Characterization Protocol (MAN-077-DDCP) and the Pre-Demolition Survey Plan for D&D Facilities (MAN-127-PDSP). The PDS is built upon physical, chemical and radiological hazards identified in the facility-specific Historical Site Assessment Report and Reconnaissance Level Characterization Report for the Group A facilities, dated October 14, 1999, Revision 0.

1.1 Purpose

The purpose of this report is to communicate and document the results of the Building 910 PDS effort. A PDS is performed prior to building demolition to define the final radiological and chemical conditions of a facility. Final conditions are compared with the release limits for radiological and non-radiological contaminants. PDS results will enable project personnel to make final disposition decisions, develop related worker health and safety controls, and estimate waste volumes by waste types.

1.2 Scope

This report presents the final radiological and chemical conditions of Building 910. Environmental media beneath and surrounding the facilities are not within the scope of this PDSR and will be addressed in accordance with the Soil Disturbance Permit process and in compliance with RFCA.

1.3 Data Quality Objectives

The Data Quality Objectives (DQOs) used in designing this PDS were the same DQOs identified in the Pre-Demolition Survey Plan for D&D Facilities (MAN-127-PDSP). Refer to section 2.0 of MAN-127-PDSP for these DQOs.

EXECUTIVE SUMMARY

A Pre-Demolition Survey (PDS) was performed to enable compliant disposition and waste management of Building 910. Because this Type 2 building will be demolished, the characterization was performed in accordance with the Pre-Demolition Survey Plan (MAN-127-PDSP). Building surfaces characterized as part of this PDS included the walls, ceilings, and roofs. Environmental media beneath and surrounding the facilities were not within the scope of this PDS and will be addressed in accordance with the Soil Disturbance Permit process and in compliance with RFCA.

The PDS encompassed both radiological and chemical characterization to enable compliant disposition and waste management pursuant to the D&D Characterization Protocol (MAN-077-DDCP). The characterization built upon physical, chemical and radiological hazards identified in the facility-specific Historical Site Assessment Report and Reconnaissance Level Characterization Report for the Group A facilities.

Results indicate that no radiological or chemical contamination exists in excess of the PDSP unrestricted release limits, except for two sand-filter tanks in the basement of B910. The sand filter tanks have been drained of liquids, are radiologically clean on the outside but contain very low levels of residual transuranic and uranium contamination on the inside. The two sand-filter tanks were sealed and will be removed and packaged as radioactive waste during the demolition of the building. Building 910 was initially proposed to be a RCRA Unit, however, RCRA waste was never introduced into the facility, and a permitted unit was never established. In the RLCR, building materials suspected of containing non-friable asbestos were "None Detected", however, friable, asbestos-containing material (5% to 8% Chrysotile) was identified in the vapor barrier mastic coating on the thermal systems insulation. Prior to demolition, the asbestos containing material will be removed in accordance with Colorado Department of Public Health and Environment (CDPHE) Regulation 8. All beryllium results obtained during the PDS were below the investigative level of $0.1 \mu\text{g}/100\text{cm}^2$. Any potentially PCB-containing fluorescent light ballast and hazardous waste items (e.g., mercury thermostats, fluorescent light bulbs, mercury vapor light bulbs, mercury-containing gauges, circuit boards, leaded glass, and lead-acid batteries) were previously removed from the building and therefore, do not impact decontamination and decommissioning activities.

Based upon the PDSR, the Building 910 structure can be demolished and the waste managed as PCB Bulk Product waste or as sanitary waste, and the concrete can be used for backfill on-site per the RFCA RSOP for Recycling Concrete. To ensure that the facility remains free of contamination and that PDS data remain valid, isolation controls have been established, and the area has been posted accordingly.

ABBREVIATIONS/ACRONYMS

ACM	Asbestos Containing Material
Be	Beryllium
CDPHE	Colorado Department of Public Health and the Environment
DCGL _{EMC}	Derived Concentration Guideline Level – elevated measurement comparison
DCGL _w	Derived Concentration Guideline Level – Wilcoxon Rank Sum Test
D&D	Decontamination and Decommissioning
DDCP	Decontamination and Decommissioning Characterization Protocol
DOE	U.S. Department of Energy
DPP	Decommissioning Program Plan
DQA	Data quality assessment
DQOs	Data quality objectives
EPA	U.S. Environmental Protection Agency
FDPMP	Facility Disposition Program Manual
HVAC	Heating, ventilation, air conditioning
HSAR	Historical Site Assessment Report
HEUN	Highly Enriched Uranyl Nitrate
IHSS	Individual Hazardous Substance Site
IWCP	Integrated Work Control Package
K-H	Kaiser-Hill
LBP	Lead-based paint
LLW	Low-level waste
MARSSIM	Multi-Agency Radiation Survey and Site Investigation Manual
MDA	Minimum detectable activity
MDC	Minimum detectable concentration
NORM	Naturally occurring radioactive material
NRA	Non-Rad-Added Verification
OSHA	Occupational Safety and Health Administration
PARCC	Precision, accuracy, representativeness, comparability and completeness
PCBs	Polychlorinated Biphenyls
PDS	Pre-demolition survey
QC	Quality Control
RCRA	Resource Conservation and Recovery Act
RFCA	Rocky Flats Cleanup Agreement
RFETS	Rocky Flats Environmental Technology Site
RFFO	Rocky Flats Field Office
RLC	Reconnaissance Level Characterization
RLCR	Reconnaissance Level Characterization Report
RSA	Removable Surface Activity
RSP	Radiological Safety Practices
SVOCs	Semi-volatile organic compounds
TCLP	Toxicity Characteristic Leaching Procedure
TSA	Total surface activity
VOCs	Volatile organic compounds

TABLE OF CONTENTS

ABBREVIATIONS/ACRONYMS	IV
EXECUTIVE SUMMARY	V
1 INTRODUCTION	1
1.1 PURPOSE.....	1
1.2 SCOPE.....	1
1.3 DATA QUALITY OBJECTIVES.....	1
2 HISTORICAL SITE ASSESSMENT	2
3 RADIOLOGICAL CHARACTERIZATION AND HAZARDS	2
4 CHEMICAL CHARACTERIZATION AND HAZARDS	3
4.1 ASBESTOS	4
4.2 BERYLLIUM (BE).....	4
4.3 RCRA/CERCLA CONSTITUENTS [INCLUDING METALS AND VOLATILE ORGANIC COMPOUNDS (VOCs)].....	4
4.4 POLYCHLORINATED BIPHENYLS (PCBS).....	5
5 PHYSICAL HAZARDS	5
6 DATA QUALITY ASSESSMENT	5
7 DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES	6
8 FACILITY CLASSIFICATION AND CONCLUSIONS.....	6
9 REFERENCES	7

ATTACHMENTS








- A Facility Location Map
- B Radiological Data Summaries and Survey Maps
- C Chemical Data Summaries and Sample Maps
- D Data Quality Assessment (DQA) Detail

ATTACHMENT A

Facility Location Map

Area 2 Building 910

Standard Map Features


-  Buildings and other structures
-  Solar Evaporation Ponds (SEPs)
-  Lakes and ponds
-  Streams, ditches, or other drainage features
-  Fences and other barriers
-  Paved roads
-  Dirt roads

DATA SOURCE BASE FEATURES:
Buildings, fences, hydrography, roads and other structures from 1994 aerial fly-over data captured by EG&G RSL, Las Vegas. Digitized from the orthophotographs, 1/95

Scale = 1 : 12450
1 inch represents approximately 1038 feet
250 500 1000 ft
State Plane Coordinate Projection
Colorado Central Zone
Datum: NAD27

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by:
DynCorp
THE ART OF TECHNOLOGY
Prepared for:
Kaiser Aluminum
November 14, 2001
Map ID: FY 2003



ATTACHMENT B

Radiological Data Summaries and Survey Maps

SURVEY UNIT 910-A-002
RADIOLOGICAL DATA SUMMARY - PDS

Survey Unit Description: B910 (Interior)

910-A-002
PDS Data Summary

Total Surface Activity Measurements

	30	31
	Number Required	Number Obtained
MIN	-6.5	dpm/100 cm ²
MAX	48.2	dpm/100 cm ²
MEAN	13.0	dpm/100 cm ²
STD DEV	13.5	dpm/100 cm ²
TRANSURANIC DCGL _w	100	dpm/100 cm ²

Removable Activity Measurements

	30	31
	Number Required	Number Obtained
MIN	-1.2	dpm/100 cm ²
MAX	6.7	dpm/100 cm ²
MEAN	-0.1	dpm/100 cm ²
STD DEV	1.5	dpm/100 cm ²
TRANSURANIC DCGL _w	20	dpm/100 cm ²

**SURVEY UNIT 910-A-002
TSA - DATA SUMMARY**

Manufacturer:	NE Tech	NE Tech	NE Tech	NE Tech	NE Tech	NE Tech
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	1	2	3	7	9	10
Serial #:	394	394	2344	2344	3125	1366
Cal Due Date:	1/12/03	1/12/03	1/17/03	1/17/03	4/21/03	4/30/03
Analysis Date:	11/4/02	11/4/02	11/4/02	11/5/02	11/7/02	11/7/02
Alpha Eff. (c/d):	0.225	0.225	0.220	0.220	0.213	0.194
Alpha Bkgd (cpm)	1.0	1.0	1.0	0.7	2.0	1.3
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm ²)	48.0	48.0	48.0	48.0	48.0	48.0

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	Sample Gross Activity (dpm/100cm ²)	LAB Gross Counts (cpm)	LAB Gross Activity (dpm/100cm ²)	Sample Net Activity (dpm/100cm ²) ^{1,2}
1	1	10	44.4	7.3	32.4	29.1
2	1	2	8.9	2	8.9	-6.5
3	3	14	63.6	4	18.2	48.2
4	7	6	27.3	2	9.1	11.9
5	1	10.7	47.6	6	26.7	32.2
6	9	11.3	53.1	4	18.8	37.7
7	9	4	18.8	4	18.8	3.4
8	10	6.7	34.5	4.7	24.2	19.1
9	7	2	9.1	0.7	3.2	-6.3
10	7	2.7	12.3	2	9.1	-3.1
11	9	8	37.6	0.7	3.3	22.2
12	1	5	22.2	6	26.7	6.8
13	3	3.3	15.0	3.3	15.0	-0.4
14	7	5.3	24.1	3.3	15.0	8.7
15	10	5.3	27.3	4.7	24.2	11.9
16	1	9.3	41.3	5.3	23.6	25.9
17	1	8.7	38.7	2.7	12.0	23.3
18	1	5.3	23.6	3.3	14.7	8.2
19	1	6	26.7	6	26.7	11.3
20	9	6.7	31.5	2.7	12.7	16.1
21	9	6.7	31.5	4.3	20.2	16.1
22	9	8	37.6	4	18.8	22.2
23	9	6.7	31.5	2	9.4	16.1
24	9	8	37.6	4	18.8	22.2
25	9	2.7	12.7	1.3	6.1	-2.7
26	9	2.7	12.7	3.3	15.5	-2.7
27	9	6.7	31.5	2.7	12.7	16.1
28	9	5.3	24.9	2.7	12.7	9.5
29	9	2	9.4	2	9.4	-6.0
30	9	3.3	15.5	1.3	6.1	0.1
12A (under carpet)	1	6	26.7	1	4.4	11.3

1 - Average LAB used to subtract from Gross Sample Activity

15.4	Sample LAB Average
MIN	-6.5
MAX	48.2
MEAN	13.0
SD	13.5
Transuranic DCGL _w	100

QC Measurements

5 QC	10	3.3	17.0	1.3	6.7	6.7
16 QC	10	6.7	34.5	2.7	13.9	24.2

1 - Average QC LAB used to subtract from Gross Sample Activity

10.3	QC LAB Average
MIN	6.7
MAX	24.2
MEAN	15.5
Transuranic DCGL _w	100

**SURVEY UNIT 910-A-002
RSC - DATA SUMMARY**

Manufacturer:	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	5	6	11	12
Serial #:	959	963	833	963
Cal Due Date:	1/18/03	1/3/03	2/28/03	1/3/03
Analysis Date:	11/4/02	11/4/02	11/7/02	11/7/02
Alpha Eff. (c/d):	0.33	0.33	0.33	0.33
Alpha Bkgd (cpm)	0.3	0.3	0.4	0.1
Sample Time (min)	2	2	2	2
Bkgd Time (min)	10	10	10	10
MDC (dpm/100cm²)	9.0	9.0	9.0	9.0

Sample Location Number	Instrument ID#	Gross Counts (cpm)	Net Activity (dpm/100 cm ²)
1	5	0	-0.9
2	6	1	0.6
3	5	1	0.6
4	12	1	1.2
5	6	0	-0.9
6	12	1	1.2
7	11	0	-1.2
8	11	0	-1.2
9	13	0	0.0
10	11	0	-1.2
11	13	0	0.0
12	6	0	-0.9
13	5	0	-0.9
14	11	0	-1.2
15	12	0	-0.3
16	5	5	6.7
17	6	0	-0.9
18	5	0	-0.9
19	6	0	-0.9
20	11	0	-1.2
21	13	0	0.0
22	11	0	-1.2
23	12	0	-0.3
24	13	0	0.0
25	11	0	-1.2
26	11	1	0.3
27	12	1	1.2
28	13	0	0.0
29	13	1	1.5
30	12	0	-0.3
12A(under carpet)	5	0	-0.9
		MIN	-1.2
		MAX	6.7
		MEAN	-0.1
		SD	1.5
		Transuranic DCGL _w	20

20

PRE-DEMOLITION SURVEY FOR B910

Survey Area: 2

Survey Unit: 910-A-002

Classification: 3

Building: 910


Survey Unit Description: Interior

Total Area: 3087 sq. m.

Total Floor Area: 856 sq. m.

PAGE 1 OF 2

B910 Interior



SURVEY MAP LEGEND


- Smear & TSA Location
- Smear, TSA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Scan Survey Information

Survey Instrument ID #(s) & RCT ID #(s):

8, 9, 10



1 inch = 30 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

Prepared for:

DynCorp

THE ART OF TECHNOLOGY

MAP ID: 03-0046/B910-IN1-SC

Nov 12, 2002

PRE-DEMOLITION SURVEY FOR B910

Survey Area: 2

Survey Unit: 910-A-002

Classification: 3

Building: 910


Survey Unit Description: Interior

Total Area: 3087 sq. m.

Total Floor Area: 856 sq. m.

PAGE 2 OF 2

B910 Basement



Scan Area


SURVEY MAP LEGEND

- Smear & TSA Location
- Smear, TSA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Scan Survey Information

Survey Instrument ID #(s) & RCT ID #(s):
8, 9, 10



1 inch = 30 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-866-7707

Prepared for:

DynCorp
THE ART OF TECHNOLOGY

MAP ID: 03-0046/B910-IN2-SC

Nov 12, 2002

☒ Property
 ☐ Waste
 ☐ Sample

RELEASE EVALUATION FORM

Page 1 of 15
 Release Evaluation No.: 021101-00883-003 EXTENDED: No EXPIRES: N/A Charge No.: N/A

PART I

SENDER/CUSTODIAN ACKNOWLEDGEMENT

Description of Property/Waste/Sample To Be Released/Transferred:

Building 910 – All re-sale items removed from B910 including pumps, motors, stainless steel valves, air compressors, and associated components produced during the removal of these items.

NOTE: This release evaluation does not pertain to the Sand Filter Tanks.

Current Location: B910

Destination: RFETS, PU & D (Dick Link, x4220 - RE Point-of-Contact)

New Recipient/Custodian: Same as above

History/Process Knowledge:


The materials described in this release evaluation were never used for the intended purpose. Building 910 was constructed to process and treated the liquid waste from the RFETS Solar Ponds. However, Solar Pond water was never processed and the systems in B910 were never used for the intended purpose. A test run was performed on the system, after which the system was shut-down and never used again.

Pre-job surveys performed prior to the generation of this release evaluation show no presence of DOE controlled radioactive materials.

Therefore, there is a very low potential for DOE controlled radioactive materials to be present on this equipment and materials.

Has the specified material ever been in an RBA/CA or contacted DOE controlled radioactive materials? NO

- 1) By signing below, I certify information provided in Part I of this release evaluation to be true and accurate.
- 2) By signing below, I agree to comply with the specific requirements noted in Part II of this release evaluation.

Sender/Custodian: Emp. No: Date: 11 Nov 02Ext: 6436

☒ Property

☐ Waste

☐ Sample

RELEASE EVALUATION FORM

Page 2 of 15

Release Evaluation No.: 021101-00883-003 EXTENDED: No EXPIRES: N/A Charge No.: N/A

PART II RADIOLOGICAL ENGINEERING

SPECIFIC REQUIREMENTS AND/OR COMMENTS:

SURVEYS REQUIRED

The B910 system and associated material have met all of the requirements for potential unrestricted release from radiological controls.

Historical assessment information on B910 present a limited concern for this material to contain or be contaminated with DOE controlled radioactive materials. Detailed sampling and surveys SHALL performed on this equipment.

- Custodian, retain a copy of all documents required by this release evaluation. The sender/custodian will be responsible for ensuring a copy of this release evaluation is available for auditing/due diligence purposes.

WHEN LINES OR PIPING ARE REMOVED, PROJECT SHALL REMOVE EACH SECTION OF LINE AND PLACE ONTO FLOOR IN A MANNER AS TO PROVIDE EVENTUAL ACCESS TO RCT FOR SURVEYS TO BE PERFORMED. For example, the lines should not be piled into a jumbled mess that would prevent the technician from gaining safe access to all areas of the lines; lines should be placed onto ground in as organized a manner as practical.

1. **HEAT EXCHANGERS, VACUUM CHAMBERS, & MEMS UNITS:** RCT, perform a 10% scan (minimum) on all accessible surfaces of the items. Obtain a minimum of five (5) fixed and removable activity surveys on the interior surfaces of each unit. ALSO, obtain additional investigative surveys based on initial results at the discretion of the RCT.
2. **TANKS, FILTRATION CHAMBERS:** RCT, perform 10% scan (minimum) on all accessible surfaces of the items. Obtain a minimum of five (5) fixed and removable activity surveys on areas of collection, tank outlets, and other areas that show a potential for accumulating material during process.
3. **FEED & DRAIN PIPING SURVEYS:** RCT, perform a 10% scan of all accessible surfaces of the piping. Obtain ten (10) fixed activity measurements AND ten (10) removable activity measurements on the interior surfaces of the piping.

(NOTE, piping diameter should be large enough to place an NE Electra probe inside the pipe. Contact Radiological Engineering R. Neveau, x3461 if this assumption is not true).

RCT shall use professional judgement on the need to obtain any additional fixed activity measurements based on results of field measurements.

Forward all surveys to Radiological Engineering for final review prior to placing any items or objects associated with this D&D activity into its final shipping waste container.

Evaluated: Rock Neveau Emp. No. [REDACTED] Date: 11-01-02 Ext: 3461
Radiological Engineer

APPROVAL FOR TRANSFER/SHIPMENT

Approved: J.P. Titus Emp. No. [REDACTED] Date: 11/11/02 Ext: 5825
Radiological Engineer

PROPERTY/WASTE RELEASE EVALUATION SIGNATURE REQUIREMENTSRelease Evaluation #: 021101-00883-003Page ~~4~~ of 15³
R.N.**Release Evaluation for Waste:**

A Release Evaluation for Waste requires an evaluation and unrestricted release approval signature. The evaluation signature is by the Radiological Engineer (RE) providing the methods or criteria for unrestricted release (i.e., survey requirements, analytical requirements, no survey required, etc.). The unrestricted release approval signature for a Release Evaluation for Waste shall be a RE authorized to provide unrestricted release approval. In addition, the evaluation and unrestricted release approval signatures shall not be the same RE. The intent of this provision is to provide peer review of the evaluation and method of unrestricted release. It is important the RE take the peer review process seriously and not become a "rubber stamp" for their fellow engineer.

Release Evaluation for Property:

A Release Evaluation for Property requires an evaluation and unrestricted release approval signature. For a Release Evaluation for Property, the evaluation and unrestricted release signature may be the same RE. In the past, only one signature was required for property for which a RE could provide an unrestricted release on the basis of process knowledge/history.

Release Evaluation for Samples:

Samples are any waste or material that is being shipped to an off-site facility for analysis. Samples that may be provided with an unrestricted release using process knowledge/history or standard contamination survey techniques may be authorized for shipment to an off-site facility using the signatory requirements specified for property. Samples which cannot be provided with an unrestricted release using process knowledge/history or standard contamination survey techniques shall be authorized for shipment from the Site using the methodology specified for waste, i.e., second signature being provided by a RE authorized to perform peer review and approval for shipment.

The approval for transfer/shipment section of a Sample Release Evaluation (SRE) shall be revised as noted below for samples which cannot be provide with an unrestricted release.

"The samples specified in Part 1 of this release evaluation are being provided with authorization for transport as non-radioactive materials in accordance with Department of Transportation (49 CFR) regulation. This authorization for shipment does not constitute an unrestricted release."

Additional Documentation:

Number of lines per section may be modified or additional pages attached to ensure adequate documentation of information necessary to perform release evaluation.

Additional pages or attachments to a release evaluation shall have the evaluation number, Page of , initials of Radiological Engineer signing approval for transfer/shipment and date.

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2316
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	12/11/02
Bkg.	0.2 cpm	Bkg.	35 cpm	Bkg.	A-1.0 B-768(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-200 B-307
MDA	20 dpm	MDA	200 dpm	MDA	A-37 B-429(dpm)
Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency	↓	Efficiency	↓	Efficiency	↓
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type: Contamination

COPY

Building: 910

Location: First Floor Valve and piping

Purpose: Job coverage

RWP #: 02-883-0009

Date: 11/01/02 Time: 1100

RCT: B. Jestes / B. Jestes
Print name / Signature

RCT: N/A / N/A / N/A
Print name Signature Emp. #

PRE/REN #: N/A 02/10/01-00883-003

Comments: Isotope of concern: Pu

p. 4 of 15 A.N.

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
2	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
3	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
4	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
5	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
6	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
7	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
8	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
9	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
10	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
11	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
12	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
13	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
14	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
15	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
17	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
18	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
19	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

ite Reviewed: 11-4-02 RS Supervision: J. Helms

Print Name

Signature

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE


RADIOLOGICAL SAFETY

Drawing Showing Survey Points

COPY

PRE# 021101-00003-003

p. 5 of 15



27

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2319
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	1/10/03
Bkg.	0.0 cpm	Bkg.	38 cpm	Bkg.	A-4.0 B-846(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-.232 B-.333
MDA	20 dpm	MDA	200 dpm	MDA	A-52 B-415(dpm)
Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency	↓	Efficiency	↓	Efficiency	↓
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type: Contamination

COPY

Building: 910

Location: 2" pipe removal

Purpose: Job coverage

RWP #: 02-883-0009

Date: 10/31/02 Time: 1600

RCT: B. Jestes / *[Signature]* Emp. # [REDACTED]

Print name Signature

RCT: N/A / N/A / N/A

Print name Signature Emp. #

PRE/REN #: N/A 02/101-00583-003

Comments: Isotope of concern: Pu

Removal of 2" S.S. piping in basement

p. 6 of 15

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
2	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
3	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
4	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
5	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
6	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
7	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
8	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
9	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
10	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
11	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
12	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
13	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
14	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
15	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
17	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
18	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
19	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

ate Reviewed: 11-4-02 RS Supervision: J. Helms

Print Name

Signature

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	772	Serial#	2314
Cal Due	1/13/03	Cal Due	6/19/03	Cal Due	4/8/03
Bkg.	0.2 cpm	Bkg.	33 cpm	Bkg.	A-5.0 B-862(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-231 B-.320
MDA	20 dpm	MDA	200 dpm	MDA	A-57 B-435(dpm)
Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency		Efficiency		Efficiency	
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type:

Contamination

COPY

Building: 910

Location: Basement Tanks

Purpose: Job coverage

RWP #: 02-883-0009

Date: 10/30/02 Time: 1530

RCT: B. Jestes / *B. Jestes* / [REDACTED]

Print name Signature Emp. #

RCT: N/A / N/A / N/A

Print name Signature Emp. #

PRE/REN #: N/A 021101-00883-003

p. 7 of —

Comments: Isotope of concern: Pu

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	See Map	<20	<200	<57	<435	21	See Map	<20	<200	<57	<435
2	See Map	<20	<200	<57	<435	22	See Map	<20	<200	<57	<435
3	See Map	<20	<200	<57	<435	23	See Map	<20	<200	<57	<435
4	See Map	<20	<200	<57	<435	24	See Map	<20	<200	<57	<435
5	See Map	<20	<200	<57	<435	25	See Map	<20	<200	<57	<435
6	See Map	<20	<200	<57	<435	26	See Map	<20	<200	<57	<435
7	See Map	<20	<200	<57	<435	27	See Map	<20	<200	<57	<435
8	See Map	<20	<200	<57	<435	28	See Map	<20	<200	<57	<435
9	See Map	<20	<200	<57	<435	29	See Map	<20	<200	<57	<435
10	See Map	<20	<200	<57	<435	30	See Map	<20	<200	<57	<435
11	See Map	<20	<200	<57	<435	31	See Map	<20	<200	<57	<435
12	See Map	<20	<200	<57	<435	32	See Map	<20	<200	<57	<435
13	See Map	<20	<200	<57	<435	33	See Map	<20	<200	<57	<435
14	See Map	<20	<200	<57	<435	34	See Map	<20	<200	<57	<435
15	See Map	<20	<200	<57	<435	35	See Map	<20	<200	<57	<435
16	See Map	<20	<200	<57	<435	36	See Map	<20	<200	<57	<435
17	See Map	<20	<200	<57	<435	37	See Map	<20	<200	<57	<435
18	See Map	<20	<200	<57	<435	38	See Map	<20	<200	<57	<435
19	See Map	<20	<200	<57	<435	39	See Map	<20	<200	<57	<435
20	See Map	<20	<200	<57	<435	40	See Map	<20	<200	<57	<435

Date Reviewed: 11-1-02 RS Supervision: J. Helms


Print Name

Signature


Emp. #

Drawing Description



PRE#: 021101-00863-003 p.8 of 15



D-12




D-12



D-6

PRE# : 021101-00853-003 p.9 of 15



ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

COPY

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2319
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	1/10/03
Bkg.	0.3 cpm	Bkg.	39 cpm	Bkg.	A-4.0 B-898(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-232 B-333
MDA	20 dpm	MDA	200 dpm	MDA	A-52 B-427(dpm)
Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency	↓	Efficiency	↓	Efficiency	↓
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type:		Contamination:	
Building: 910			
Location: First Floor Tank and Filters			
Purpose: Job coverage			
RWP #:		02-883-0009	
Date: 10/29/02		Time: 1540	
RCT:	B. Jestes	/	<i>B. Jestes</i>
	Print name		Signature
RCT:	N/A	/	N/A
	Print name		Signature
			Emp. #

PRE/REN #: N/A 021101-00883-003 *p. 10 of 15*

Comments: Isotope of concern: Pu

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	D-52, 1" nipple	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
2	D-52	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
3	D-52	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
4	D-52	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
5	D-52, 1" nipple	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
6	D-52, flange	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
7	D-52, flange	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
8	Filter, O/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
9	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
10	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
11	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
12	Filter, O/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
13	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
14	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
15	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
17	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
18	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
19	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A



ate Reviewed: 11-1-02 RS Supervision: J. Helms *[Signature]*

Print Name Signature

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

RADIOLOGICAL SAFETY

Drawing Showing Survey Points *PROJ: 02/01-00883-003 p. 11 of 15*



ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

COPY

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2319
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	1/10/03
Bkg.	0.3 cpm	Bkg.	39 cpm	Bkg.	A-4.0 B-898(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-232 B-.333
MDA	20 dpm	MDA	200 dpm	MDA	A-52 B-427(dpm)

Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency	↓	Efficiency	↓	Efficiency	↓
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type: Contamination

Building: 910
 Location: 1st floor vacuum chambers (VC) and MEMS Units
 Purpose: Job coverage

RWP #: 02-883-0009

Date: 10/29/02 Time: 1530

RCT: B. Jestes / *B. Jestes*
 Print name Signature

RCT: N/A / N/A / N/A
 Print name Signature Emp. #

PRE/REN #: N/A 02/10/01-00883-003

Comments: Isotope of concern: Pu

A total of (3) vacuum chambers (VC) and (3) MEMS Units were surveyed.

Survey locations and results typical for all heat exchangers and MEMS Units surveyed.

SURVEY RESULTS

(Results in dpm / 100cm²)


#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
2	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
3	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
4	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
5	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
6	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
7	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
8	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
9	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
10	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
11	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
12	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
13	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
14	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
15	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
16	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
17	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
18	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
19	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
20	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A

ate Reviewed: 10-31-02 RS Supervision: J. Helms
 Print Name



Signature

PRE#: 021101-0083-003

0.13 of 15



VIEW: Unit (Front view)



20 inch side

COPY

Survey Type: Contamination

Building: 910

Location: Outside pad

Purpose: sample hose contents / drain

RWP #: 02-883-0009

Date: 10-28-02 Time: 1100

RCT: B Jester / B Jester
Print name Signature

RCT: N/A / N/A
Print name Signature Emp. #

SURVEY RESULTS

Map

The diagrams are hand-drawn sketches. The first diagram shows a cross-section of a hose with two internal circles labeled 1 and 3. The second diagram shows a side view of a cap with four internal circles labeled 2, 3, 4, and 5. The third diagram shows two horizontal lines representing a hose with a break, indicated by a zigzag line, with circles 6 and 7 at the break points.

Hose, typ.
female

cap, end
male

PRO-164-RSP-07.01 (effective 7/12/01)

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	NE-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	971	Serial#	910	Serial#	2319
Cal Due	1-15-03	Cal Due	7-2-03	Cal Due	1-10-03
Bkg.	0.0 cpm	Bkg.	40 cpm	Bkg.	50 205 G (cpm)
Efficiency	33%	Efficiency	25%	Efficiency	123.20 13330
MDA	20 dpm	MDA	200 dpm	MDA	570 420 (dpm)

Mfg. <u>NA</u>	Mfg. <u>NA</u>	Mfg. <u>NA</u>
Model <u>NA</u>	Model <u>NA</u>	Model <u>NA</u>
Serial# <u>NA</u>	Serial# <u>NA</u>	Serial# <u>NA</u>
Cal Due <u>NA</u>	Cal Due <u>NA</u>	Cal Due <u>NA</u>
Bkg. <u>NA</u>	Bkg. <u>NA</u>	Bkg. <u>NA</u>
Efficiency <u>NA</u>	Efficiency <u>NA</u>	Efficiency <u>NA</u>
MDA <u>NA</u>	MDA <u>NA</u>	MDA <u>NA</u>

Survey Type: Contamination **COPY**
Building: 910
Location: Outside x-fer pipes / hoses
Purpose: Release

RWP #: 02-883-0009

Date: 10-24-02 Time: 1330

RCT: B Jester / B Jester
Print name Signature


Print name NA / Signature NA / Emp. # NA

PRN/REN #: NA 021101-00883-003 p. 15 of 15
Comments: Breach of hose - tanker side connection

SURVEY RESULTS

Swipe #	Location/Description Results in dpm/100cm ²	Removable		Direct	
		Alpa	Beta	Alpa	Beta
1	Cop	L20	L200	L57	L428
2	Cop	L20	L200	L57	L428
3	Hose gasket	L20	L200	L57	L428
4	E/S hose	L20	L200	L57	L428
5	edge	L20	L200	L57	L428
NA	NA	NA	NA	NA	NA
V	V	V	V	V	V
NA	NA	NA	NA	NA	NA

Map



Date Reviewed: 10-29-02 RS Supervision: J. Helms
Print Name

Signature

Standard Air Sample Analysis Form

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Breach of feedwater lines top& bottom level RWP#: 02-883-009

Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-78 79 NA 11-4-02
Location	Top & bottom level
Sample Model/Serial #	LoVol/ # 9998
Sampler Calibration Due Date	3/16/03
Date / Time On	10/31/02 12:30
Date / Time Off	10/31/02 14:30
Total Run Time (min)	120
Average Flow Rate (lpm or cfm)	4 cfm
m3/min = (lpm x .001 or cfm x .0283)	0.1132
Volume V=m3/min x time	13.58

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/31/02
Instrument Model / Serial #	Sac 4 / 818
Efficiency	33.00%
Instrument Calibration Due Date	3/20/03
Total Count	3107
Count Duration (min)	10
Gross Count Rate (cpm)	310.7
Background Count Rate (cpm)	0.3
Net Count Rate (cpm)	310.4
Net Activity (C1) in dpm	931.2

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	11/4/02-0900	N/A
Instrument Model / Serial #	N/A	Sac 4/ 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	4	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.4	N/A
Background Count Rate (cpm)	N/A	0.4	N/A
Net Count Rate (cpm)	N/A	0	N/A
Net Activity (C2) in dpm	N/A	0	N/A

(with Koval)

(if C2 ≥ C1)

(Field Screen)

$$\text{DAC} = \frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(\text{DACREF})}$$

$$\text{DAC} = \frac{C2}{(V)(CF)(\text{DACREF})}$$

$$\text{DAC} = \frac{C1}{(V)(CF)(\text{DACREF})}$$

(low volume)

(CAM/SAAM)

(FAH)

(lapel)

CF=0.7

CF=1.0

CF=0.7

CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	>72	N/A
DAC REF	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL Factor (K)	N/A	N/A	N/A
Calculated DAC:	17.18	0	N/A
RCT Printed Name	L. Severtson	L Severtson	N/A
RCT Signature	<i>[Signature]</i>	<i>[Signature]</i>	N/A
			N/A

Approved by:

RS Supervision

J. Helms

[Signature]

Print Name

Signature

11-4-02

Date

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Breach of HX east bank RWP#: 02-883-009

Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-76-77-A	11-4-02
Location	Top floor	
Sample Model/Serial #	LoVol/ # 9998	
Sampler Calibration Due Date	3/16/03	
Date / Time On	10/29/02 13:30	
Date / Time Off	10/29/02 14:00	
Total Run Time (min)	30	
Average Flow Rate (lpm or cfm)	3.5 cfm	
m3/min = (lpm x .001 or cfm x .0283)	0.0849	
Volume = m3/min x time	2.55	

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/29/02	
Instrument Model / Serial #	Sac 4 / 818	
Efficiency	33.00%	
Instrument Calibration Due Date	3/20/03	
Total Count	443	
Count Duration (min)	10	
Gross Count Rate (cpm)	44.3	
Background Count Rate (cpm)	0.6	
Net Count Rate (cpm)	43.7	
Net Activity (D2) in dpm	131.1	

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	10/30/02-13:30	N/A
Instrument Model / Serial #	N/A	Sac 4/ 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	4	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.4	N/A
Background Count Rate (cpm)	N/A	0.1	N/A
Net Count Rate (cpm)	N/A	0.3	N/A
Net Activity (D2) in dpm	N/A	0.9	N/A

(with Koval)

(if C2>C1)

(Field Screen)

DAC = $\frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$

DAC = $\frac{C2}{(V)(CF)(DACREF)}$

DAC = $\frac{C1}{(V)(CF)(DACREF)}$

(low volume)

(CAM/SAAM)

(FAH)

(lapel)

CF=0.7

CF=1.0

CF=0.7

CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	24	N/A
DAC REF	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL Factor (K)	N/A	N/A	N/A
Calculated DAC:	12.80	0.088	N/A
RCT Printed Name	L. Severtson	L. Severtson	N/A
RCT Signature	<i>L. Severtson</i>	<i>L. Severtson</i>	N/A
			N/A

Approved by:

RS Supervision

J. Heums

Print Name

[Signature]

Signature

11-4-02

Date

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Breach of HX west bank RWP#: 02-883-009Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-77 78 JA		
Location	Top floor		
Sample Model/Serial #	LoVol/ # 9998		
Sampler Calibration Due Date	3/16/03		
Date / Time On	10/29/02 14:00		
Date / Time Off	10/29/02 14:30		
Total Run Time (min)	30		
Average Flow Rate (lpm or cfm)	3.5 cfm		
m3/min = (lpm x .001 or cfm x .0283)	0.0849		
	2.55		

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/29/02		
Instrument Model / Serial #	Sac 4 / 818		
Efficiency	33.00%		
Instrument Calibration Due Date	3/20/03		
Total Count	679		
Count Duration (min)	10		
Gross Count Rate (cpm)	67.9		
Background Count Rate (cpm)	0.6		
Net Count Rate (cpm)	67.3		
Net Activity (CPM) in dpm	201.9		

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	11/1/02	N/A
Instrument Model / Serial #	N/A	Sac 4/ 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	5	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.5	N/A
Background Count Rate (cpm)	N/A	0.3	N/A
Net Count Rate (cpm)	N/A	0.2	N/A
Net Activity (CPM) in dpm	N/A	0.6	N/A

(with Koval)

(if C2 ≥ C1)

(Field Screen)

DAC = $\frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$

DAC = $\frac{C2}{(V)(CF)(DACREF)}$

DAC = $\frac{C1}{(V)(CF)(DACREF)}$

(low volume)

(CAM/SAAM)

(FAH)

(lapel)

CF=0.7

CF=1.0

CF=0.7

CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	>72	N/A
DAC REF	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL FACTOR (K)	N/A	N/A	N/A
Calculated DAC:	19.85	0.059	N/A
RCT Printed Name	L. Severtson	L. Severtson	N/A
RCT Signature	<i>L. Severtson</i>	<i>L. Severtson</i>	N/A
			N/A

Approved by:

RS Supervision

J. Hems

1 *[Signature]*

1

111-4-02

Print Name

Signature

Date

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Removal of Filter Equipment RWP#: 02-883-009
 Isotope: Pu Inhalation Class: W Filter Media: 47mm

Sample ID #	200273	2	3
Location	Outside	N/A	N/A
Sample Model / Serial #	Low Vol. / #9998	N/A	N/A
Sampler Calibration Due Date	Prior to Use / Weekly	N/A	N/A
Date / Time On	10/24/02 15:10	N/A	N/A
Date / Time Off	10/24/02 15:24	N/A	N/A
Total Run Time (min)	14	N/A	N/A
Average Flow Rate (lpm or cfm)	3	N/A	N/A
m3/min = (lpm x .001 or cfm x .0283)	0.0849	N/A	N/A
	1.19	N/A	N/A

FIRST COUNT ANALYSIS DATA:

Date	10/24/02	N/A	N/A
Time (t3)	1545	N/A	N/A
Instrument Model / Serial #	SAC-4 / # 1156	N/A	N/A
Instrument Calibration Due Date	1/13/03	N/A	N/A
Total Count	2410	N/A	N/A
Count Duration (min)	10	N/A	N/A
Gross Count Rate (cpm)	241	N/A	N/A
Background Count Rate (cpm)	0.1	N/A	N/A
Net Count Rate (cpm)	240.9	N/A	N/A
	722.7		

SECOND COUNT ANALYSIS DATA:

Date	10/28/02	N/A	N/A
Time (t4)	0730	N/A	N/A
Instrument Model / Serial #	SAC-4 / # 1196	N/A	N/A
Instrument Calibration Due Date	1/13/02	N/A	N/A
Total Count	5	N/A	N/A
Count Duration (min)	10	N/A	N/A
Gross Count Rate (cpm)	0.5	N/A	N/A
Background Count Rate (cpm)	0.4	N/A	N/A
Net Count Rate (cpm)	0.1	N/A	N/A
	0.3		

(with Koval)

$$DAC = \frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$$

(if $C2 \geq C1$)

$$DAC = \frac{C2}{(V)(CF)(DACREF)}$$

(Field Screen)

$$DAC = \frac{C1}{(V)(CF)(DACREF)}$$

(low volume)

(CAM/SAAM)

(FAH)

(lapel)

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

CF=0.7

CF=1.0

CF=0.7

CF=1.0 or 0.7

m3/min = lpm x 0.001

lpm = CFM/0.0353

	1st Count	2nd Count	1st Count	2nd Count	1st Count	2nd Count
Decay Time (t4-t3) in Hours	N/A	772.7	N/A	N/A	N/A	N/A
	4.8		N/A		N/A	
	0.7		N/A		N/A	
	N/A				N/A	
Calculated DAC:	180.96	0.08	N/A	N/A	N/A	N/A
RCT Printed Name	B. Jestes		N/A		N/A	
RCT Signature	<i>B. Jestes</i>		N/A		N/A	
			N/A		N/A	

Approved by:

RS Supervision

J. Helms

Print Name

Signature

Date

10-29-02

Standard Air Sample Analysis Form

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Piping & hose removal RWP#: 02-883-009

Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-74		
Location	Norh side of bldg.		
Sample Model/Serial #	LoVol/ # 9998		
Sampler Calibration Due Date	3/16/03		
Date / Time On	10/28/02 10:25		
Date / Time Off	10/28/02 11:15		
Total Run Time (min)	50		
Average Flow Rate (lpm or cfm)	3 cfm		
m3/min = (lpm x .001 or cfm x .0283)	0.0849		
Volume V=m3/min x time	4.25		

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/28/02		
Instrument Model / Serial #	Sac 4 / 818		
Efficiency	33.00%		
Instrument Calibration Due Date	3/20/03		
Total Count	3348		
Count Duration (min)	10		
Gross Count Rate (cpm)	334.8		
Background Count Rate (cpm)	0.4		
Net Count Rate (cpm)	334.4		
Net Activity (C1) in dpm	1003.2		

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	11/1/02-10:00	N/A
Instrument Model / Serial #	N/A	Sac 4 / 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	4	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.4	N/A
Background Count Rate (cpm)	N/A	0.3	N/A
Net Count Rate (cpm)	N/A	0.1	N/A
Net Activity (C2) in dpm	N/A	0.3	N/A

(with Koval)

(if C2>C1)

(Field Screen)

DAC = $\frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$

DAC = $\frac{C2}{(V)(CF)(DACREF)}$

DAC = $\frac{C1}{(V)(CF)(DACREF)}$

(low volume)

(CAM/SAAM)

(FAH)

(lapel)

CF=0.7

CF=1.0

CF=0.7



CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	>72	N/A
DAC REF	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL Factor (K)	N/A	N/A	N/A
Calculated DAC:	59.40	0.018	N/A
RCT Printed Name	L. Severtson	L Severtson	N/A
RCT Signature			N/A
			N/A

Approved by:

RS Supervision

J. HELMS

1/11/02

1

111-4-02

Print Name

Signature

Date



Property



Waste



Sample

RELEASE EVALUATION FORMPage 1 of 15Release Evaluation No.: 021101-00883-002 EXTENDED: No EXPIRES: N/A Charge No.: N/A**PART I****SENDER/CUSTODIAN ACKNOWLEDGEMENT****Description of Property/Waste/Sample To Be Released/Transferred:**

Building 910 – Process feed & drain lines associated with all system components for the B910 filtration system. This includes any valves, flanges, tanks (excluding the Sand Tanks), distillate tanks & system components, transfer hoses, vacuum chambers, piping, or other system components. Also included is the wires, cables, support structures, and any associated incidental cabinets, furniture, trash, or waste produced during the removal of these items.

NOTE: This release evaluation does not pertain to the Sand Filter Tanks.

Current Location: B910

Destination: Front Range Landfill, 1830 Weld County Road 5, Erie, CO, 80112

New Recipient/Custodian: Same as above

History/Process Knowledge:


The materials described in this release evaluation were never used for the intended purpose. Building 910 was constructed to process and treated the liquid waste from the RFETS Solar Ponds. However, Solar Pond water was never processed and the systems in B910 were never used for the intended purpose. A test run was performed on the system, after which the system was shut-down and never used again.

Pre-job surveys performed prior to the generation of this release evaluation show no presence of DOE controlled radioactive materials.

Therefore, there is a very low potential for DOE controlled radioactive materials to be present on this equipment and materials.

Has the specified material ever been in an RBA/CA or contacted DOE controlled radioactive materials? NO

- 1) By signing below, I certify information provided in Part I of this release evaluation to be true and accurate.
- 2) By signing below, I agree to comply with the specific requirements noted in Part II of this release evaluation.

Sender/Custodian: Emp. No: Date: 01/11/02 Ext: 6438

☐ Property

☒ Waste

☐ Sample

RELEASE EVALUATION FORM

Page 2 of 15

Release Evaluation No.: 021101-00883-002 EXTENDED: No EXPIRES: N/A Charge No.: N/A

PART II RADIOLOGICAL ENGINEERING

SPECIFIC REQUIREMENTS AND/OR COMMENTS:

SURVEYS REQUIRED

The B910 system and associated material have met all of the requirements for potential unrestricted release from radiological controls.

Historical assessment information on B910 present a limited concern for this material to contain or be contaminated with DOE controlled radioactive materials. Detailed sampling and surveys SHALL performed on this equipment.

- Custodian, retain a copy of all documents required by this release evaluation. The sender/custodian will be responsible for ensuring a copy of this release evaluation is available for auditing/due diligence purposes.

WHEN LINES OR PIPING ARE REMOVED, PROJECT SHALL REMOVE EACH SECTION OF LINE AND PLACE ONTO FLOOR IN A MANNER AS TO PROVIDE EVENTUAL ACCESS TO RCT FOR SURVEYS TO BE PERFORMED. For example, the lines should not be piled into a jumbled mess that would prevent the technician from gaining safe access to all areas of the lines; lines should be placed onto ground in as organized a manner as practical.

1. **HEAT EXCHANGERS, VACUUM CHAMBERS, & MEMS UNITS:** RCT, perform a 10% scan (minimum) on all accessible surfaces of the items. Obtain a minimum of five (5) fixed and removable activity surveys on the interior surfaces of each unit. ALSO, obtain additional investigative surveys based on initial results at the discretion of the RCT.
2. **TANKS, FILTRATION CHAMBERS:** RCT, perform 10% scan (minimum) on all accessible surfaces of the items. Obtain a minimum of five (5) fixed and removable activity surveys on areas of collection, tank outlets, and other areas that show a potential for accumulating material during process.
3. **FEED & DRAIN PIPING SURVEYS:** RCT, perform a 10% scan of all accessible surfaces of the piping. Obtain ten (10) fixed activity measurements AND ten (10) removable activity measurements on the interior surfaces of the piping.

(NOTE, piping diameter should be large enough to place an NE Electra probe inside the pipe. Contact Radiological Engineering R. Neveau, x3461 if this assumption is not true).

RCT shall use professional judgement on the need to obtain any additional fixed activity measurements based on results of field measurements.

Forward all surveys to Radiological Engineering for final review prior to placing any items or objects associated with this D&D activity into its final shipping waste container.

Evaluated: Rick Neveau / [Signature] Emp. No. [Redacted] Date: 11-01-02 Ext: 3461
Radiological Engineer

APPROVAL FOR TRANSFER/SHIPMENT

Approved: [Signature] / J.P. Titus Emp. No. [Redacted] Date: 11/11/02 Ext: 5825
Radiological Engineer

PROPERTY/WASTE RELEASE EVALUATION SIGNATURE REQUIREMENTSRelease Evaluation #: 021101-00883-002Page ~~4~~ of 15

3

LN

Release Evaluation for Waste:

A Release Evaluation for Waste requires an evaluation and unrestricted release approval signature. The evaluation signature is by the Radiological Engineer (RE) providing the methods or criteria for unrestricted release (i.e., survey requirements, analytical requirements, no survey required, etc.). The unrestricted release approval signature for a Release Evaluation for Waste shall be a RE authorized to provide unrestricted release approval. In addition, the evaluation and unrestricted release approval signatures shall not be the same RE. The intent of this provision is to provide peer review of the evaluation and method of unrestricted release. It is important the RE take the peer review process seriously and not become a "rubber stamp" for their fellow engineer.

Release Evaluation for Property:

A Release Evaluation for Property requires an evaluation and unrestricted release approval signature. For a Release Evaluation for Property, the evaluation and unrestricted release signature may be the same RE. In the past, only one signature was required for property for which a RE could provide an unrestricted release on the basis of process knowledge/history.

Release Evaluation for Samples:

Samples are any waste or material that is being shipped to an off-site facility for analysis. Samples that may be provided with an unrestricted release using process knowledge/history or standard contamination survey techniques may be authorized for shipment to an off-site facility using the signatory requirements specified for property. Samples which cannot be provided with an unrestricted release using process knowledge/history or standard contamination survey techniques shall be authorized for shipment from the Site using the methodology specified for waste, i.e., second signature being provided by a RE authorized to perform peer review and approval for shipment.

The approval for transfer/shipment section of a Sample Release Evaluation (SRE) shall be revised as noted below for samples which cannot be provide with an unrestricted release.

"The samples specified in Part 1 of this release evaluation are being provided with authorization for transport as non-radioactive materials in accordance with Department of Transportation (49 CFR) regulation. This authorization for shipment does not constitute an unrestricted release."

Additional Documentation:

Number of lines per section may be modified or additional pages attached to ensure adequate documentation of information necessary to perform release evaluation.

Additional pages or attachments to a release evaluation shall have the evaluation number, Page ___ of ___, initials of Radiological Engineer signing approval for transfer/shipment and date.


ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2316
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	12/11/02
Bkg.	0.2 cpm	Bkg.	35 cpm	Bkg.	A-1.0 B-768(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-.200 B-.307
MDA	20 dpm	MDA	200 dpm	MDA	A-37 B-429(dpm)
Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency	↓	Efficiency	↓	Efficiency	↓
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type: Contamination

COPY

Building: 910
 Location: First Floor Valve and piping
 Purpose: Job coverage
 RWP #: 02-883-0009
 Date: 11/01/02 Time: 1100
 RCT: B. Jestes / *B. Jestes* / 
 Print name Signature Emp. #
 RCT: N/A / N/A / N/A
 Print name Signature Emp. #

PRE/REN #: N/A 02 1101-00883-002 p. 4 of 15

Comments: Isotope of concern: Pu

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
2	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
3	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
4	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
5	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
6	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
7	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
8	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
9	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
10	See map	<20	<200	<37	<429	N/A	N/A	N/A	N/A	N/A	N/A
11	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
12	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
13	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
14	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
15	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
17	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
18	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
19	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Date Reviewed: 11-4-02 RS Supervision: J. Helms

Print Name

Signature

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE


RADIOLOGICAL SAFETY

Drawing Showing Survey Points

COPY

REF#: 021101-00883-001

p. 5 of 15



ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2319
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	1/10/03
Bkg.	0.0 cpm	Bkg.	38 cpm	Bkg.	A-4.0 B-846(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-232 B-333
MDA	20 dpm	MDA	200 dpm	MDA	A-52 B-415(dpm)

Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency	↓	Efficiency	↓	Efficiency	↓
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type: Contamination

COPY

Building: 910
 Location: 2" pipe removal
 Purpose: Job coverage

RWP #: 02-883-0009

Date: 10/31/02 Time: 1600

RCT: B. Jestes / *B. Jestes* / [REDACTED]
 Print name Signature Emp. #

RCT: N/A / N/A / N/A
 Print name Signature Emp. #

PRE/REN #: N/A *PRE#: 024101-00883-002 p. 6 of 15*

Comments: Isotope of concern: Pu

Removal of 2" S.S. piping in basement

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
2	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
3	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
4	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
5	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
6	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
7	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
8	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
9	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
10	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
11	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
12	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
13	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
14	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
15	Piping	<20	<200	<52	<415	N/A	N/A	N/A	N/A	N/A	N/A
16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
17	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
18	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
19	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Date Reviewed: 11-4-02 RS Supervision: J. Helms

Print Name

Signature

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	772	Serial#	2314
Cal Due	1/13/03	Cal Due	6/19/03	Cal Due	4/8/03
Bkg.	0.2 cpm	Bkg.	33 cpm	Bkg.	A-5.0 B-862(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-231 B-320
MDA	20 dpm	MDA	200 dpm	MDA	A-57 B-435(dpm)
Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency	↓	Efficiency	↓	Efficiency	↓
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type: Contamination

COPY

Building: 910
 Location: Basement Tanks
 Purpose: Job coverage

RWP #: 02-883-0009

Date: 10/30/02 Time: 1530

RCT: B. Jestes / *B. Jestes*
 Print name Signature

RCT: N/A / N/A / N/A
 Print name Signature Emp. #

PRE/REN #: N/A 02/10/0083-002

Comments: Isotope of concern: Pu

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	See Map	<20	<200	<57	<435	21	See Map	<20	<200	<57	<435
2	See Map	<20	<200	<57	<435	22	See Map	<20	<200	<57	<435
3	See Map	<20	<200	<57	<435	23	See Map	<20	<200	<57	<435
4	See Map	<20	<200	<57	<435	24	See Map	<20	<200	<57	<435
5	See Map	<20	<200	<57	<435	25	See Map	<20	<200	<57	<435
6	See Map	<20	<200	<57	<435	26	See Map	<20	<200	<57	<435
7	See Map	<20	<200	<57	<435	27	See Map	<20	<200	<57	<435
8	See Map	<20	<200	<57	<435	28	See Map	<20	<200	<57	<435
9	See Map	<20	<200	<57	<435	29	See Map	<20	<200	<57	<435
10	See Map	<20	<200	<57	<435	30	See Map	<20	<200	<57	<435
11	See Map	<20	<200	<57	<435	31	See Map	<20	<200	<57	<435
12	See Map	<20	<200	<57	<435	32	See Map	<20	<200	<57	<435
13	See Map	<20	<200	<57	<435	33	See Map	<20	<200	<57	<435
14	See Map	<20	<200	<57	<435	34	See Map	<20	<200	<57	<435
15	See Map	<20	<200	<57	<435	35	See Map	<20	<200	<57	<435
16	See Map	<20	<200	<57	<435	36	See Map	<20	<200	<57	<435
17	See Map	<20	<200	<57	<435	37	See Map	<20	<200	<57	<435
18	See Map	<20	<200	<57	<435	38	See Map	<20	<200	<57	<435
19	See Map	<20	<200	<57	<435	39	See Map	<20	<200	<57	<435
20	See Map	<20	<200	<57	<435	40	See Map	<20	<200	<57	<435

Date Reviewed: 11-1-02 RS Supervision: J. Helms

Print Name

Signature

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

RADIOLOGICAL SAFETY

Drawing Showing Survey Points

COPY

PRE#: 021101-00883-00 2

p. 8 of 15

Tank D-12

Tank D-2

DISTILLATE
BATCH TANK

15 14 13 12

11

D-6

DISTILLATE
BATCH TANK

Tank D-6

17 18 19 20

16

ROCKY PLANT ENVIRONMENTAL TECHNOLOGY SITE


RADIOLOGICAL SAFETY

Drawing Showing Survey Points

COPY

PRE#: 021101-00883-002


p. 9 of 15



Tank D-7



Tank D-9



Tank D-10

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2319
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	1/10/03
Bkg.	0.3 cpm	Bkg.	39 cpm	Bkg.	A-4.0 B-898(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-232 B-333
MDA	20 dpm	MDA	200 dpm	MDA	A-52 B-427(dpm)
Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency		Efficiency		Efficiency	
MDA	N/A	MDA	N/A	MDA	N/A


Survey Type: Contamination

COPY

Building: 910
 Location: First Floor Tank and Filters
 Purpose: Job coverage

RWP #: 02-883-0009

Date: 10/29/02 Time: 1540

RCT: B. Jestes / *B. Jestes* / 
 Print name Signature Emp. #

RCT: N/A / N/A / N/A
 Print name Signature Emp. #

PRE/REN #: N/A 021101-00883-002

Comments: Isotope of concern: Pu

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	D-52, 1" nipple	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
2	D-52	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
3	D-52	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
4	D-52	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
5	D-52, 1" nipple	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
6	D-52, flange	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
7	D-52, flange	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
8	Filter, O/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
9	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
10	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
11	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
12	Filter, O/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
13	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
14	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
15	Filter, I/S	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
16	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
17	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
18	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
19	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
20	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A

Date Reviewed: 11-1-02 RS Supervision: J. Helms

Print Name

Signature

Emp. #


PRO-164-RSP-07.01 (effective 7/12/01)

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

RADIOLOGICAL SAFETY

Drawing Showing Survey Points PRE#: 021101-00863-002

0. 11 01-15



ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

COPY

INSTRUMENT DATA

Mfg.	Eberline	Mfg.	Eberline	Mfg.	Ne-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	1156	Serial#	773	Serial#	2319
Cal Due	1/13/03	Cal Due	9/18/03	Cal Due	1/10/03
Bkg.	0.3 cpm	Bkg.	39 cpm	Bkg.	A-4.0 B-898(cpm)
Efficiency	33 %	Efficiency	25%	Efficiency	A-.232 B-.333
MDA	20 dpm	MDA	200 dpm	MDA	A-52 B-427(dpm)

Mfg.	N/A	Mfg.	N/A	Mfg.	N/A
Model		Model		Model	
Serial#		Serial#		Serial#	
Cal Due		Cal Due		Cal Due	
Bkg.		Bkg.		Bkg.	
Efficiency		Efficiency		Efficiency	
MDA	N/A	MDA	N/A	MDA	N/A

Survey Type: Contamination

Building: 910

Location: 1st floor vacuum chambers (VC) and MEMS Units

Purpose: Job coverage

RWP #: 02-883-0009

Date: 10/29/02

Time: 1530

RCT: B. Jestes

Print name

Signature

RCT: N/A

Print name

N/A

Signature

N/A

Emp. #

PRE/REN #: N/A 62/101-00883-002

p/2 of 15

Comments: Isotope of concern: Pu

A total of (3) vacuum chambers (VC) and (3) MEMS Units were surveyed.

Survey locations and results typical for all heat exchangers and MEMS Units surveyed.

SURVEY RESULTS

(Results in dpm / 100cm²)

#	Location / Description	Removable		Direct		#	Location / Description	Removable		Direct	
		Alpha	Beta	Alpha	Beta			Alpha	Beta	Alpha	Beta
1	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
2	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
3	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
4	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
5	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
6	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
7	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
8	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
9	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
10	Vacuum chamb.	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
11	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
12	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
13	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
14	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
15	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
16	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
17	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
18	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
19	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A
20	MEMS Unit	<20	<200	<52	<427	N/A	N/A	N/A	N/A	N/A	N/A

Date Reviewed: 10-31-02

RS Supervision:

J. Helms

Print Name

Signature

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE


RADIOLOGICAL SAFETY

Drawing Showing Survey Points


COPY

PR# 021101-0003-002


p 13 of 15



MEMS Unit (Front View)



VC unit, front



VC unit, side

6-PRO-164-RSP-07.01 (effective 7/12/01)

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE
TRUIMENT DATA

INSTRUMENT DATA

INSTRUMENT DATA					
Mfg.	Eberline	Mfg.	Eberline	Mfg.	NE-Tech
Model	SAC-4	Model	BC-4	Model	Electra
Serial#	971	Serial#	910	Serial#	2319
Cal Due	1-15-03	Cal Due	7-2-03	Cal Due	1-10-03
Bkg.	0.0 cpm	Bkg.	40 cpm	Bkg.	50 205 G (cpm)
Efficiency	33%	Efficiency	25%	Efficiency	123.20 133.30
MDA	20 dpm	MDA	200 dpm	MDA	570 420 (dpm)

Mfg. <u>NA</u>	Mfg. <u>NA</u>	Mfg. <u>NA</u>
Model <u>NA</u>	Model <u>NA</u>	Model <u>NA</u>
Serial# <u>NA</u>	Serial# <u>NA</u>	Serial# <u>NA</u>
Cal Due <u>NA</u>	Cal Due <u>NA</u>	Cal Due <u>NA</u>
Bkg. <u>NA</u>	Bkg. <u>NA</u>	Bkg. <u>NA</u>
Efficiency <u>NA</u>	Efficiency <u>NA</u>	Efficiency <u>NA</u>
MDA <u>NA</u>	MDA <u>NA</u>	MDA <u>NA</u>

Survey Type: Contamination

COPY

Building: 910

Location: Outside x-fer pipes / hoses
Purpose: P.L.

Purpose: Release

RWP #: 02-883-0009

Date: 10-24-02

Time: 1330

RCT: B. Jester 1 B. Jester
Print name Signature

RCT: NA / NA / NA
Print name Signature Emp. #


PRN/REN #: NA 021101-00863-002 p.15 of 15
Comments:

Comments: Breach of hose - tanker side connection

SURVEY RESULTS

[illegible]

Map



Date Reviewed: 10-29-02 RS Supervision: J. HELMS
Print Name

Signature

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Removal of Filter Equipment RWP#: 02-883-009Isotope: Pu Inhalation Class: W Filter Media: 47mm

Sample ID #	200273	2	3
Location	Outside	N/A	N/A
Sample Model / Serial #	Low Vol. / #9998	N/A	N/A
Sampler Calibration Due Date	Prior to Use / Weekly	N/A	N/A
Date / Time On	10/24/02 15:10	N/A	N/A
Date / Time Off	10/24/02 15:24	N/A	N/A
Total Run Time (min)	14	N/A	N/A
Average Flow Rate (lpm or cfm)	3	N/A	N/A
m3/min = (lpm x .001 or cfm x .0283)	0.0849	N/A	N/A
	1.19	N/A	N/A

FIRST COUNT ANALYSIS DATA:

Date	10/24/02	N/A	N/A
Time (t3)	1545	N/A	N/A
Instrument Model / Serial #	SAC-4 / # 1156	N/A	N/A
Instrument Calibration Due Date	1/13/03	N/A	N/A
Total Count	2410	N/A	N/A
Count Duration (min)	10	N/A	N/A
Gross Count Rate (cpm)	241	N/A	N/A
Background Count Rate (cpm)	0.1	N/A	N/A
Net Count Rate (cpm)	240.9	N/A	N/A
	722.7		

SECOND COUNT ANALYSIS DATA:

Date	10/28/02	N/A	N/A
Time (t4)	0730	N/A	N/A
Instrument Model / Serial #	SAC-4 / # 1196	N/A	N/A
Instrument Calibration Due Date	1/13/02	N/A	N/A
Total Count	5	N/A	N/A
Count Duration (min)	10	N/A	N/A
Gross Count Rate (cpm)	0.5	N/A	N/A
Background Count Rate (cpm)	0.4	N/A	N/A
Net Count Rate (cpm)	0.1	N/A	N/A
	0.3		

(with Koval)

(if C2 ≥ C1)

(Field Screen)

$$\text{DAC} = \frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(\text{DACREF})}$$

$$\text{DAC} = \frac{C2}{(V)(CF)(\text{DACREF})}$$

$$\text{DAC} = \frac{C1}{(V)(CF)(\text{DACREF})}$$

(low volume)

(CAM/SAAM)

(FAH)

(lapel)

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

CF=0.7

CF=1.0

CF=0.7

CF=1.0 or 0.7

m3/min = lpm x 0.001

lpm = CFM/0.0353

	1st Count	2nd Count	1st Count	2nd Count	1st Count	2nd Count
Decay Time (t4-t3) in Hours	N/A	772	N/A		N/A	
	4.8		N/A		N/A	
	0.7		N/A		N/A	
	N/A				N/A	
Calculated DAC:	180.96	0.08	N/A	N/A	N/A	N/A
RCT Printed Name	B.Jestes		N/A		N/A	
RCT Signature	<i>B.Jestes</i>		N/A		N/A	
			N/A		N/A	

Approved by:
RS SupervisionJ. Helms
Print Name

Signature

Date

1/10-29-02

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Piping & hose removal RWP#: 02-883-009Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-74
Location	North side of bldg.
Sample Model/Serial #	LoVol/ # 9998
Sampler Calibration Due Date	3/16/03
Date / Time On	10/28/02 10:25
Date / Time Off	10/28/02 11:15
Total Run Time (min)	50
Average Flow Rate (lpm or cfm)	3 cfm
m3/min = (lpm x .001 or cfm x .0283)	0.0849
Volume (m3) = Run Time (min) x Flow Rate (m3/min)	4.25

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/28/02
Instrument Model / Serial #	Sac 4 / 818
Efficiency	33.00%
Instrument Calibration Due Date	3/20/03
Total Count	3348
Count Duration (min)	10
Gross Count Rate (cpm)	334.8
Background Count Rate (cpm)	0.4
Net Count Rate (cpm)	334.4
Net Activity (Ci) = (cpm / 3700)	1003.2

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	11/1/02-10:00	N/A
Instrument Model / Serial #	N/A	Sac 4 / 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	4	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.4	N/A
Background Count Rate (cpm)	N/A	0.3	N/A
Net Count Rate (cpm)	N/A	0.1	N/A
Net Activity (Ci) = (cpm / 3700)	N/A	0.3	N/A

(with Koval)

$$DAC = \frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$$
(if $C2 \geq C1$)
$$DAC = \frac{C2}{(V)(CF)(DACREF)}$$

(Field Screen)

$$DAC = \frac{C1}{(V)(CF)(DACREF)}$$

(low volume)

CF=0.7

(CAM/SAAM)

CF=1.0

(FAH)

CF=0.7

(lapel)

CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	>72	N/A
DAC REF	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL Factor (K)	N/A	N/A	N/A
Calculated DAC:	59.40	0.018	N/A
RCT Printed Name	L. Severtson	L. Severtson	N/A
RCT Signature	<i>[Signature]</i>	<i>[Signature]</i>	N/A
			N/A

Approved by:

RS Supervision

J. HELMS

Print Name

[Signature]

Signature

111-402

Date

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Breach of HX east bank RWP#: 02-883-009Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-76 77-M
Location	Top floor
Sample Model/Serial #	LoVol/ # 9998
Sampler Calibration Due Date	3/16/03
Date / Time On	10/29/02 13:30
Date / Time Off	10/29/02 14:00
Total Run Time (min)	30
Average Flow Rate (lpm or cfm)	3.5 cfm
m3/min = (lpm x .001 or cfm x .0283)	0.0849
Volume = m3/min x time	2.55

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/29/02
Instrument Model / Serial #	Sac 4 / 818
Efficiency	33.00%
Instrument Calibration Due Date	3/20/03
Total Count	443
Count Duration (min)	10
Gross Count Rate (cpm)	44.3
Background Count Rate (cpm)	0.6
Net Count Rate (cpm)	43.7
Net Activity (Ci) in dpm	131.1

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	10/30/02-13:30	N/A
Instrument Model / Serial #	N/A	Sac 4/ 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	4	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.4	N/A
Background Count Rate (cpm)	N/A	0.1	N/A
Net Count Rate (cpm)	N/A	0.3	N/A
Net Activity (Ci) in dpm	N/A	0.9	N/A

(with Koval)

$$DAC = \frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$$

(if $C2 \geq C1$)

$$DAC = \frac{C2}{(V)(CF)(DACREF)}$$

(Field Screen)

$$DAC = \frac{C1}{(V)(CF)(DACREF)}$$

(low volume)

CF=0.7

(CAM/SAAM)

CF=1.0

(FAH)

CF=0.7

(lapel)

CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	24	N/A
DAC REF	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL Factor (K)	N/A	N/A	N/A

Calculated DAC:

12.80

0.088

N/A

RCT Printed Name

L. Severtson

L Severtson

N/A

RCT Signature

[Signature]

[Signature]

N/A

Approved by:

RS Supervision

J. Heums

1

[Signature]

1

11-4-02

Print Name

Signature

Date

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

 Bldg # 910 Purpose: Breach of HX west bank RWP#: 02-883-009

 Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-77 78 JA		
Location	Top floor		
Sample Model/Serial #	LoVol/ # 9998		
Sampler Calibration Due Date	3/16/03		
Date / Time On	10/29/02 14:00		
Date / Time Off	10/29/02 14:30		
Total Run Time (min)	30		
Average Flow Rate (lpm or cfm)	3.5 cfm		
m3/min = (lpm x .001 or cfm x .0283)	0.0849		
Volume = (m3/min) x time	2.55		

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/29/02		
Instrument Model / Serial #	Sac 4 / 818		
Efficiency	33.00%		
Instrument Calibration Due Date	3/20/03		
Total Count	679		
Count Duration (min)	10		
Gross Count Rate (cpm)	67.9		
Background Count Rate (cpm)	0.6		
Net Count Rate (cpm)	67.3		
Net Activity (C/min dpm)	201.9		

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	11/1/02	N/A
Instrument Model / Serial #	N/A	Sac 4/ 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	5	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.5	N/A
Background Count Rate (cpm)	N/A	0.3	N/A
Net Count Rate (cpm)	N/A	0.2	N/A
Net Activity (C/min dpm)	N/A	0.6	N/A

(with Koval)

$$DAC = \frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$$

(if C2 > C1)

$$DAC = \frac{C2}{(V)(CF)(DACREF)}$$

(Field Screen)

$$DAC = \frac{C1}{(V)(CF)(DACREF)}$$

(low volume)

CF=0.7

(CAM/SAAM)

CF=1.0

(FAH)

CF=0.7

(lapel)

CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	>72	N/A
DAC	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL Factor (K)	N/A	N/A	N/A
Calculated DAC:	19.85	0.059	N/A
RCT Printed Name	L. Severtson	L. Severtson	N/A
RCT Signature	<i>L. Severtson</i>	<i>L. Severtson</i>	N/A
			N/A

Approved by:

RS Supervision

J. Helms

Print Name

Signature

1/11-4-02

Date

Standard Air Sample Analysis Form

COPY

Low-Volume / SAAM / CAM / FAH / Lapel Air Samples

Bldg # 910 Purpose: Breach of feedwater lines top& bottom level RWP#: 02-883-009

Isotope: PU Inhalation Class: W Filter Media: 47 mm glass

Sample ID #	2002-78 79 JA	
Location	Top & bottom level	
Sample Model/Serial #	LoVol/ # 9998	
Sampler Calibration Due Date	3/16/03	
Date / Time On	10/31/02 12:30	
Date / Time Off	10/31/02 14:30	
Total Run Time (min)	120	
Average Flow Rate (lpm or cfm)	4 cfm	
m3/min = (lpm x .001 or cfm x .0283)	0.1132	
	13.58	

FIRST COUNT ANALYSIS DATA:

Date/Time (t3)	10/31/02	
Instrument Model / Serial #	Sac 4 / 818	
Efficiency	33.00%	
Instrument Calibration Due Date	3/20/03	
Total Count	3107	
Count Duration (min)	10	
Gross Count Rate (cpm)	310.7	
Background Count Rate (cpm)	0.3	
Net Count Rate (cpm)	310.4	
Net Activity (Bq) (lpm)	931.2	

SECOND COUNT ANALYSIS DATA:

Date/Time (t4)	N/A	11/4/02-0900	N/A
Instrument Model / Serial #	N/A	Sac 4/ 818	N/A
Efficiency	N/A	33.00%	N/A
Instrument Calibration Due Date	N/A	3/20/03	N/A
Total Count	N/A	4	N/A
Count Duration (min)	N/A	10	N/A
Gross Count Rate (cpm)	N/A	0.4	N/A
Background Count Rate (cpm)	N/A	0.4	N/A
Net Count Rate (cpm)	N/A	0	N/A
Net Activity (Bq) (lpm)	N/A	0	N/A

(with Koval)

(if C2>C1)

(Field Screen)

DAC = $\frac{C2 - (C1 \times K)}{(1-K)(V)(CF)(DACREF)}$

DAC = $\frac{C2}{(V)(CF)(DACREF)}$

DAC = $\frac{C1}{(V)(CF)(DACREF)}$

(low volume)

(CAM/SAAM)

(FAH)

(lapel)

CF=0.7

CF=1.0

CF=0.7

CF=1.0 or 0.7

lpm = CFM/0.0353

CFM = lpm x 0.0353

m3/min = CFM x 0.0283

m3/min = lpm x 0.001

Decay Time (t4-t3) in Hours	N/A	>72	N/A
DAC REF	5.7	5.7	N/A
Correction Factor (CF)	0.7	0.7	N/A
KOVAL Factor (K)	N/A	N/A	N/A
Calculated DAC:	17.18	0	N/A
RCT Printed Name	L. Severtson	L. Severtson	N/A
RCT Signature	<i>[Signature]</i>	<i>[Signature]</i>	N/A
			N/A

Approved by:

RS Supervision

J. Helms

Print Name

[Signature]

Signature

11-4-02

Date

SURVEY UNIT 910-B-001
RADIOLOGICAL DATA SUMMARY - PDS

Survey Unit Description: B910 (Exterior)

910-B-001
PDS Data Summary

Total Surface Activity Measurements

	30	30
	Number Required	Number Obtained
MIN	0.0	dpm/100 cm ²
MAX	82.7	dpm/100 cm ²
MEAN	36.5	dpm/100 cm ²
STD DEV	25.1	dpm/100 cm ²
TRANSURANIC DCGL _w	100	dpm/100 cm ²

Removable Activity Measurements

	30	30
	Number Required	Number Obtained
MIN	0.0	dpm/100 cm ²
MAX	1.5	dpm/100 cm ²
MEAN	0.1	dpm/100 cm ²
STD DEV	0.4	dpm/100 cm ²
TRANSURANIC DCGL _w	20	dpm/100 cm ²

**SURVEY UNIT 910-B-001
TSA - DATA SUMMARY**

Manufacturer:	NE Tech	NE Tech	NE Tech	NE Tech	NE Tech	NE Tech
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	1	4	6	10	13	15
Serial #:	2344	3125	1261	1513	1665	1366
Cal Due Date:	1/17/03	4/21/03	4/5/03	2/1/03	3/3/03	4/30/03
Analysis Date:	11/5/02	11/5/02	11/5/02	11/6/02	11/6/02	11/7/02
Alpha Eff. (c/d):	0.220	0.213	0.210	0.207	0.213	0.194
Alpha Bkgd (cpm)	0.7	2.0	0.0	2.0	3.0	1.3
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm ²)	48.0	48.0	48.0	48.0	48.0	48.0

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	Sample Gross Activity (dpm/100cm ²)	LAB Gross Counts (cpm)	LAB Gross Activity (dpm/100cm ²)	Sample Net Activity (dpm/100cm ²) ^{1,2}
1	13	6	28.2	4.7	22.1	6.1
2	6	30	95.2	4	19.0	73.2
3	6	22	104.8	5.3	25.2	82.7
4	13	19.7	92.5	4.7	22.1	70.4
5	13	8.7	40.8	4.7	22.1	18.8
6	15	6	30.9	6.7	34.5	8.9
7	15	5.3	27.3	6	30.9	5.3
8	15	4.7	24.2	4	20.6	2.2
9	13	12	56.3	3.3	15.5	34.3
10	13	16.7	78.4	4	18.8	56.4
11	13	17	79.8	4	18.8	57.8
12	1	18.7	85.0	4	18.2	63.0
13	1	20	90.9	6	27.3	68.9
14	4	11	51.6	4	18.8	29.6
15	13	8	37.6	6	28.2	15.5
16	1	11	50.0	4.7	21.4	28.0
17	1	12.7	57.7	7.3	33.2	35.7
18	1	17.3	78.6	6.7	30.5	56.6
19	6	10	47.6	3.7	17.6	25.6
20	6	9.3	44.3	4	19.0	22.2
21	6	7.3	34.8	4.7	22.4	12.7
22	13	18	84.5	2	9.4	62.5
23	13	4.7	22.1	3.3	15.5	0.0
24	13	7.3	34.3	4	18.8	12.2
25	13	8.7	40.8	3.3	15.5	18.8
26	13	18	84.5	2.7	12.7	62.5
27	13	13.3	62.4	5.3	24.9	40.4
28	13	13.3	62.4	4	18.8	40.4
29	13	19.3	90.6	4.7	22.1	68.6
30	13	8	37.6	8	37.6	15.5

1 - Average LAB used to subtract from Gross Sample Activity

2 - The initial Sample Net Activity for locations 4 and 11 was 101.8 and 108.0 dpm/100cm², respectively. These locations were re-surveyed after a decay period. Re-survey results are reported.

22.0	Sample LAB Average
MIN	0.0
MAX	82.7
MEAN	36.5
SD	25.1
Transuranic DCGL _w	100

QC Measurements

27 QC	10	7.3	35.3	2.7	13.0	15.9
25 QC	10	19.3	93.2	5.3	25.6	73.9

1 - Average QC LAB used to subtract from Gross Sample Activity

19.3	QC LAB Average
MIN	15.9
MAX	73.9
MEAN	44.9
Transuranic DCGL _w	100

**SURVEY UNIT 910-B-001
RSC - DATA SUMMARY**

Manufacturer:	Eberline	Eberline
Model:	SAC-4	SAC-4
Instrument ID#:	19	20
Serial #:	959	853
Cal Due Date:	1/18/03	2/28/03
Analysis Date:	11/8/02	11/8/02
Alpha Eff. (c/d):	0.33	0.33
Alpha Bkgd (cpm)	0.0	0.0
Sample Time (min)	2	2
Bkgd Time (min)	10	10
MDC (dpm/100cm²)	9.0	9.0


Sample Location Number	Instrument ID#	Gross Counts (cpm)	Net Activity (dpm/100 cm ²)
1	19	0	0.0
2	20	0	0.0
3	19	0	0.0
4	20	1	1.5
5	19	0	0.0
6	20	1	1.5
7	19	0	0.0
8	20	0	0.0
9	19	0	0.0
10	20	0	0.0
11	19	0	0.0
12	20	0	0.0
13	19	0	0.0
14	20	0	0.0
15	19	0	0.0
16	20	0	0.0
17	19	0	0.0
18	20	0	0.0
19	19	0	0.0
20	20	0	0.0
21	19	0	0.0
22	20	0	0.0
23	19	0	0.0
24	20	0	0.0
25	19	0	0.0
26	20	0	0.0
27	19	0	0.0
28	20	0	0.0
29	19	0	0.0
30	20	0	0.0
		MIN	0.0
		MAX	1.5
		MEAN	0.1
		SD	0.4
		Transuranic DCGL_w	20

PRE-DEMOLITION SURVEY FOR B910


Survey Area: 2 Survey Unit: 910-B-001 Classification: 2
 Building: 910
 Survey Unit Description: Exterior & Pads
 Total Area: 1695 sq. m. Total Roof Area: 432 sq. m.
 Grid Spacing for Survey Points: 11m. X 11m. Total Floor Area: 529 sq. m.

PAGE 1 OF 1


B910 Exterior




Reverse Osmosis Ponds (East of building 910)



Concrete Pads West




Exterior Walls



Scan Area

B910 Exterior Locations



STARTING POINT
FOR SQUARE
SAMPLING GRID
(X54, Y41)

Decon Emergency Pad

Concrete Pad
Northeast

Concrete Berm East (North side)



Hatch Door Pad East



Concrete Berm East (South side)




SURVEY MAP LEGEND

- Smear & TSA Location
- Smear, TSA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Scan Survey Information

Survey Instrument ID #(s) & RCT ID #(s):
2, 3, 4, 5, 7, 11, 15, 16, 17, 18



1 inch = 36 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

Prepared for:

DynCorp
THE ART OF TECHNOLOGY

MAP ID: 03-0046/B910-EX-SC

Nov 14, 2002

17

ATTACHMENT C

Chemical Data Summaries and Sample Maps

Beryllium Data Summary

Sample Number	Map Survey Point Location	Room	Sample Location	Result (ug/100 cm ²)
Building 910				
910-11122002-315-101	101	104	Top of Nitric Acid pipe	<0.1
910-11122002-315-102	102	103	Top of MCC9A electrical box	<0.1
910-11122002-315-103	103	West	Top of LDIC-2 electrical panel	<0.1
910-11122002-315-104	104	West	Edge of white angle iron brace at ceiling	<0.1
910-11122002-315-105	105	West	Top of Unit 2, Roots Compressor	<0.1
910-11122002-315-106	106	West	Top of angle iron floor brace	<0.1
910-11122002-315-107	107	West	Top of Evaporator Feed pipe	<0.1
910-11122002-315-108	108	Basement	Top of green brace	<0.1
910-11122002-315-109	109	Basement	Top of gray brace	<0.1
910-11122002-315-110	110	Basement	Top of gray, concrete pad	<0.1
910-11122002-315-111	111	Basement	J-beam brace on concrete pad	<0.1
910-11122002-315-112	112	Basement	Top of green angle brace	<0.1
910-11122002-315-113	113	Basement	Top of Distilled Water pipe	<0.1
910-11122002-315-114	114	Basement	Top of green I-beam brace	<0.1
910-11122002-315-115	115	Concrete Berm, East	Bottom of overflow basin, east side	<0.1
910-11122002-315-116	116	Concrete Pad, NE	Edge of overflow drain	<0.1
910-11122002-315-117	117	Concrete Pad, North	On concrete pad at MV9013-3	<0.1
910-11122002-315-118	118	Concrete Pad, North	Base of vertical I-beam support	<0.1
910-11122002-315-119	119	Concrete Pad, West	On concrete	<0.1
910-11122002-315-120	120	Concrete Pad, West	On concrete	<0.1


CHEMICAL SAMPLE MAP

Beryllium

Building: 910 Interior Main Level

PAGE 1 OF 2

B910 Interior




SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- RCRA/CERCLA Sample Location
- PCB Sample Location

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.



- Open/Inaccessible Area
- Area in Another Survey Unit



1 inch = 30 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

Prepared for:

DynCorp

THE ART OF TECHNOLOGY

MAP ID: 03-0046/B910-IN1-BE

Nov. 12, 2002


CHEMICAL SAMPLE MAP

Beryllium

Building: 910 Interior Basement

PAGE 2 OF 2

B910 Basement




SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- RCRA/CERCLA Sample Location
- PCB Sample Location

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

- Open/Inaccessible Area
- Area in Another Survey Unit



1 inch = 30 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

Prepared for:

DynCorp
THE ART OF TECHNOLOGY



MAP ID: 03-0046/B910-IN2-BE

Nov. 12, 2002

PRE-DEMOLITION SURVEY FOR B910

Survey Area: 2

Survey Unit: 910-B-001

Classification: 2

Building: 910

Survey Unit Description: Exterior & Pads

Total Area: 1695 sq. m.

Total Roof Area: 432 sq. m.

Grid Spacing for Survey Points: 11m. X 11m.

Total Floor Area: 529 sq. m.


PAGE 1 OF 1

B910 Exterior


Concrete Pads North




Concrete Berm North



Reverse Osmosis Ponds
(East of building 910)



B910 Exterior Locations




STARTING POINT
FOR SQUARE
SAMPLING GRID
(X54, Y41)


Decon Emergency Pad



Concrete Pad
Northeast



Concrete Pads West




East Dock

South Dock Walls

East Dock Walls
South East North

Exterior Walls



Concrete Berm East (North side)



Hatch Door Pad East



Concrete Berm East (South side)



Scan Area

SURVEY MAP LEGEND


- Smear & TSA Location
- Smear, TSA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.



Scan Survey Information

Survey Instrument ID #(s) & RCT ID #(s):
2, 3, 4, 5, 7, 11, 15, 16, 17, 18



1 inch = 36 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

Prepared for:

DynCorp

THE ART OF TECHNOLOGY



MAP ID: 03-0046/B910-EX-SC

Nov 14, 2002

72

Asbestos Data Summary

Sample Number	Map Survey Point Location	Room	Sample Location	Analytical Results
Building 910				
910-11122002-315-201	201	West	White paint on CMU, south wall	None Detected
910-11122002-315-202	202	West	White paint on CMU, west wall	None Detected
910-11122002-315-203	203	West	White paint on CMU, north wall	None Detected
910-11122002-315-204	204	West	White paint on CMU, east wall	None Detected
910-11122002-315-205	205	104	White paint on CMU, south wall	None Detected
910-11122002-315-206	206	102	White paint on CMU, east wall	None Detected
910-11122002-315-207	207	103	White paint on CMU, east wall	None Detected


CHEMICAL SAMPLE MAP

Asbestos

Building: 910 Interior Main Level

PAGE 1 OF 1

B910 Interior




SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- RCRA/CERCLA Sample Location
- PCB Sample Location

Neither the United States Government nor Kaiser Hill Co., nor DynCorp I&ET, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

- Open/Inaccessible Area
- Area in Another Survey Unit



1 inch = 30 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy
Rocky Flats Environmental Technology Site

Prepared by: GIS Dept. 303-966-7707

Prepared for:

DynCorp
THE ART OF TECHNOLOGY



MAP ID: 03-0046/B910-IN1-ASB

Nov. 12, 2002

RCRA TCLP Metals Data (RIN#02S0203)

Sample Number	Sample Location	Analytical Results
02S0203 -001	Sand Filter, Basement B910	Below regulatory Limits
02S0203 -002	Sand Filter, Basement B910	Below regulatory Limits

RCRA Toxicity Characteristic Limits (Metals)

Analyte	Regulatory limit (mg/L)
Arsenic (D004)	5.0
Barium (D005)	100.0
Cadmium (D006)	1.0
Chromium (D007)	5.0
Lead (D008)	5.0
Mercury (D009)	0.2
Selenium (D010)	1.0
Silver (D011)	5.0

**Metals Case Narrative for
Kaiser Hill
SDG# 02S0203**

Sample Analysis:

The following samples were prepared and analyzed according to the methods referenced in the "Method/Analysis Information" section of this narrative:

Sample ID	Client ID
64569001	02S0203-001.002
64569002	02S0203-002.002
1200275879	Method Blank (MB) ICP-190948/190947
1200275883	Laboratory Control Sample (LCS)
1200275881	15128-001L (63916001) Serial Dilution (SD)
1200275880	15128-001D (63916001) Sample Duplicate (DUP)
1200275882	15128-001S (63916001) Matrix Spike (MS)
1200275899	Method Blank (MB) ICP-MS-190978/190977
1200275903	Laboratory Control Sample (LCS)
1200275901	02S0203-001.002L (64569001) Serial Dilution (SD)
1200275900	02S0203-001.002D (64569001) Sample Duplicate (DUP)
1200275902	02S0203-001.002S (64569001) Matrix Spike (MS)
1200277354	Method Blank (MB) CVAA-191151/191149
1200277359	Laboratory Control Sample (LCS)
1200277356	02S0203-001.002D (64569001) Sample Duplicate (DUP)
1200277358	02S0203-001.002S (64569001) Matrix Spike (MS)

Method Analysis

Analytical Batch #:	190948, 190978, 191151
Prep Batch #:	190947, 190977, 191149
Standard Operating Procedure:	GL-MA-E-013 REV.6, GL-MA-E-014 REV.6, GL-MA-E-010 REV.10
Analytical Method:	SW846 6010B, SW846 6020, SW846 7471A
Prep Method:	SW846 3050B, SW846 3050B, SW846 7471A

76

System Configuration

The ICP analysis was performed on a Thermo Jarrell Ash 61E Trace axial-viewing inductively coupled plasma atomic emission spectrometer. The instrument is equipped with a Meinhardt nebulizer, cyclonic spray chamber, and yttrium internal standard. Operating conditions for the Trace ICP are set at a power level of 950 watts. The instrument has a peristaltic pump flow rate of 140 RPM (2.0 mL/min sample uptake rate), argon gas flows of 15 L/min and 0.5 L/min for the torch and auxiliary gases, and a pressure setting of 26 PSI for the nebulizer.

A Perkin Elmer Elan 6100E inductively coupled plasma mass spectrometer (ICP-MS) was employed to analyze the ICP-MS samples. The instrument is equipped with a cross-flow nebulizer, quadrupole mass spectrometer, and dual mode electron multiplier detector. Internal standards of scandium, germanium, indium, and tantalum were utilized to cover the mass spectrum. Operating conditions are set at 1400W power and combined argon pressures of 360 \pm 7 kPa for the plasma and auxiliary gases, and 0.85 L/min carrier gas flow, and an initial lens voltage of 5.2.

Mercury analysis was performed on a Perkin-Elmer Flow Injection Mercury System (FIMS-400) automated mercury analyzer. The instrument consists of a cold vapor atomic absorption spectrometer set to detect mercury at a wavelength of 254 nm. Sample introduction through the flow injection system is performed via a peristaltic pump at 9 mL/min and nitrogen carrier gas rate of 5 L/min.

Sample Preparation

All samples were prepared in accordance with the referenced SW846 procedures.

Calibration Information:**Initial Calibration**

Instrument calibrations are conducted using method and instrument manufacturer's specifications. All initial calibration requirements have been met for this analysis.

CRDL Standards

All CRDL standard elements met the referenced advisory control limits.

ICSA/ICSAB Requirements

All interference checks (ICSA and ICSAB) associated with this SDG met the established acceptance criteria.

Continuing Calibration Blanks (CCB) Requirements

All continuing calibration blanks (CCB) bracketing this SDG met the established acceptance criteria.

Continuing Calibration Verification (CCV) Requirements

All continuing calibration verification (CCV) standards bracketing sample analyses associated with this SDG met the recovery acceptance criteria.

Method Blank Acceptance

All preparation blanks analyzed with this SDG met the required detection limits (RDL).

LCS Recovery Statement

The laboratory control sample (LCS) met the established acceptance criteria for all elements

QC Sample Designation

Sample 15128-001 (63916001) from another SDG was designated as the quality control sample for the ICP batch. Sample 02S0203-001.002 (64569001) from SDG 63916 was designated as the quality control sample for the ICPMS and CVAA batches. The batches included a matrix spike (MS) and a sample spike duplicate (DUP). The ICP and ICP-MS batches included a serial dilution (SD) analysis, as well.

MS Recovery Statement

The percent recoveries (%R) obtained from the MS analyses are evaluated when the sample concentration is less than four times (4X) the spike concentration added. The MS met the recommended quality control acceptance criteria for percent recovery (75%-125%) for all applicable analytes, with the exceptions of antimony, calcium, silica, and zinc, as indicated by the "N" qualifiers.

Duplicate RPD Statement

The relative percent difference (RPD) obtained from the sample duplicate (DUP) is evaluated based on acceptance criteria of 20% when the sample is 5X the required detection limit (RDL). In cases where either the sample or duplicate value is less than 5X the RDL, a control of +/-RDL is used to evaluate the DUP results. All applicable analytes in duplicate sample analyses met the RPD acceptance criteria, except aluminum and silica as indicated by the "*" qualifiers.

Serial Dilution Statement

The serial dilution is used to assess interference caused by matrix suppression or enhancement. Raw element concentrations that are at least 50X the IDL for ICP and at least 100X the IDL for ICP-MS analyses are applicable for serial dilution assessment. All applicable analytes met the established criteria for serial dilution evaluation percent difference <10, with the exception of potassium, as indicated by the "E" qualifier.

Technical Information:**Holding Time Specifications**

All samples in this SDG met the specified holding time requirements.

Sample Dilutions

Dilutions are performed to minimize matrix interference resulting from elevated mineral element concentrations and/or to bring over range target analyte concentrations into the linear calibration range of the instruments. All samples were diluted the standard 2x for ICP and ICPMS analysis. The LCS was diluted the standard 5x for all analyses. No other dilutions were required.

Miscellaneous Information:**NCR Documentation**

Nonconformance reports (NCR) are generated to document procedural anomalies that may deviate from referenced SOP or contractual documents. No NCR's were generated for this SDG.

Additional Comments

The additional comments field is used to address special issues associated with each analysis, clarify method/contractual issues pertaining to the analysis and to list any report documents generated as a result of sample analysis or review.

Due to limitations of the software on the ICPMS, names such as CCV and CCB do not appear on the raw data. These instrument quality control samples must be named "QC standard x" for sequencing and check table purposes. A chart correlating the "QC standard x" to the accepted names for them has been provided in the Miscellaneous Data section of this package.

Review/Validation:

GEL requires all analytical data to be verified by a qualified data validator.

The following data validator verified the data presented in this SDG:

Reviewer: Carol M. E. 8/14/02

CASIS

RFETS

CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST

COC: 02S0203#002

Page 1 of 1

Telephone No.
4289 / 2358Purchase Order/Charge Code
EFD56501Ice Chest No.
Temp.Bill of Lading/Air Bill No.
6192 8128 5181

PRE

SCREENING SPECIAL INSTRUCTIONS

REQUIRED

Hold Time

Are acid preserved samples DOT hazardous per 40 CFR Part 136.3 Table II? YES NO

Are other known hazardous substances present? YES NO

Customer Number

Matrix

Date/Time

Location

Container (size/type)

Sample Analysis (Field-Filtered) LIC (Method Title) [TAT]/Parameter List

Preservative; Packing

Bottle No.

02S0203

-001.001

OBJECT

7/21/02 0825

BLDG. 910 SAND FILTERS

125-G

G

ASP-A-004 (Americium, Plutonium, Uranium) [14dF]

(AM241; PU23234; U235; U238)

None; None

02S0203

-001.002

OBJECT

↓

BLDG. 910 SAND FILTERS

250-G

G

MET-A-023 (METALS 6010/6010B) [14dF]

(See Item 1)

None; 4 degrees C

02S0203

-002.001

OBJECT

0830

BLDG. 910 SAND FILTERS

125-G

G

ASP-A-004 (Americium, Plutonium, Uranium) [14dF]

(AM241; PU23234; U235; U238)

None; None

02S0203

-002.002

OBJECT

↓

BLDG. 910 SAND FILTERS

250-G

G

MET-A-023 (METALS 6010/6010B) [14dF]

(See Item 1)

None; 4 degrees C

Item 1

MET-A-023: Aluminum; Antimony; Arsenic; Barium; Beryllium; Boron; Cadmium; Calcium; Chromium; Cobalt; Copper; Iron; Lead; Lithium; Magnesium; Mercury; Molybdenum; Nickel; Potassium; Selenium; Silica; Silver; Sodium; Strontium; Thallium; Tin; Titanium; Uranium; Vanadium; Zinc

Item 2

MET-A-031: Arsenic; Barium; Cadmium; Chromium; Lead; Mercury; Selenium; Silver

Relinquished By:

Date/Time

Received By:

Date/Time

Relinquished By:

Date/Time

Received By:

Date/Time

Relinquished By:

Date/Time

Received By:

Date/Time

Relinquished By:

Date/Time

Received By:

Date/Time

Relinquished By:

Date/Time

Received By:

Date/Time

Relinquished By:

Date/Time

Received By:

Date/Time

FINAL SAMPLE

DISPOSITION

Disposal Method (e.g., returned to customer, disposed of per lab procedure, used in analytical process)

Disposed By

Date/Time

Date/Time

Date/Time

Date/Time

Date/Time COC printed: 07/29/02 07:23 (Version: coc_r19.rpt)

19

TOTAL METALS
- 1 -
INORGANIC ANALYSIS DATA PACKAGE

SDG No.: 02S0203A

Method Type: SW846

Sample ID: 64570001

Client ID: 02S0203-001002

Contract: KHCO00100

Lab Code: GEL

Case No.: GEL

SAS No.:

Matrix: TCLP

Date Received: 8/1/2002

Level: LOW

% Solids: 0.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7440-38-2	Arsenic	0.040	mg/L	U		P	0.040	TJA61 Trace ICP2	80602
7440-39-3	Barium	0.060	mg/L	B		P	0.002	TJA61 Trace ICP2	80602
7440-43-9	Cadmium	0.004	mg/L	B		P	0.002	TJA61 Trace ICP2	80602
7440-47-3	Chromium	0.025	mg/L	B		P	0.005	TJA61 Trace ICP2	80602
7439-92-1	Lead	0.016	mg/L	B		P	0.012	TJA61 Trace ICP2	80602
7439-97-6	Mercury	0.001	mg/L	B		AV	0.0004	PE CVAA2	080602WIHg
7782-49-2	Selenium	0.027	mg/L	U		P	0.027	TJA61 Trace ICP2	80602
7440-22-4	Silver	0.012	mg/L	U		P	0.012	TJA61 Trace ICP2	80602

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

AKC 8/12/02

SW-8269

80

TOTAL METALS

- 1 -

INORGANIC ANALYSIS DATA PACKAGE

SDG No.: 02S0203A

Method Type: SW846

Sample ID: 64570002

Client ID: 02S0203-002.002

Contract: KHCO00100

Lab Code: GEL

Case No.: GEL

SAS No.:

Matrix: TCLP

Date Received: 8/1/2002

Level: LOW

% Solids: 0.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7440-38-2	Arsenic	0.040	mg/L	U		P	0.040	TJA61 Trace ICP2	80602
7440-39-3	Barium	0.051	mg/L	B		P	0.002	TJA61 Trace ICP2	80602
7440-43-9	Cadmium	0.002	mg/L	U		P	0.002	TJA61 Trace ICP2	80602
7440-47-3	Chromium	0.015	mg/L	B		P	0.005	TJA61 Trace ICP2	80602
7439-92-1	Lead	0.012	mg/L	U		P	0.012	TJA61 Trace ICP2	80602
7439-97-6	Mercury	0.001	mg/L	B		AV	0.0004	PE CVAA2	080602W1Hg
7782-49-2	Selenium	0.027	mg/L	U		P	0.027	TJA61 Trace ICP2	80602
7440-22-4	Silver	0.012	mg/L	U		P	0.012	TJA61 Trace ICP2	80602

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

46.2 8/12/02

SW-84670

31

TOTAL METALS

- 1 -

INORGANIC ANALYSIS DATA PACKAGE

SDG No.: 02S0203

Method Type: SW846

Sample ID: 64569001

Client ID: 02S0203-001.002

Contract: KHCO00100

Lab Code: GEL

Case No.: GEL

SAS No.:

Matrix: SOIL

Date Received: 8/1/2002

Level: LOW

% Solids: 100.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7429-90-5	Aluminum	732	mg/kg		*	P	0.613	TJA61 Trace ICP2	80702
7440-36-0	Antimony	0.474	mg/kg	U	N	P	0.474	TJA61 Trace ICP2	80702
7440-38-2	Arsenic	1.210	mg/kg	B		P	0.394	TJA61 Trace ICP2	80702
7440-39-3	Barium	40.9	mg/kg			P	0.019	TJA61 Trace ICP2	80702
7440-41-7	Beryllium	0.206	mg/kg	B		MS	0.005	PE ICPMS3	020805
7440-42-8	Boron	0.388	mg/kg	U		P	0.388	TJA61 Trace ICP2	80702
7440-43-9	Cadmium	0.608	mg/kg	B		MS	0.006	PE ICPMS3	020805
7440-70-2	Calcium	1050	mg/kg		N	P	1.560	TJA61 Trace ICP2	80702
7440-47-3	Chromium	14.3	mg/kg			P	0.053	TJA61 Trace ICP2	80702
7440-48-4	Cobalt	1.790	mg/kg	B		P	0.058	TJA61 Trace ICP2	80702
7440-50-8	Copper	16.4	mg/kg			P	0.129	TJA61 Trace ICP2	80702
7439-89-6	Iron	2240	mg/kg			P	0.209	TJA61 Trace ICP2	80702
7439-92-1	Lead	10.2	mg/kg			P	0.123	TJA61 Trace ICP2	80702
7439-93-2	Lithium	0.818	mg/kg	B		MS	0.005	PE ICPMS3	020805
7439-95-4	Magnesium	180	mg/kg	B		P	0.509	TJA61 Trace ICP2	80702
7439-96-5	Manganese	15.8	mg/kg			P	0.036	TJA61 Trace ICP2	80702
7439-97-6	Mercury	0.009	mg/kg	B		AV	0.003	PE CVAA	080302S1Hg
7439-98-7	Molybdenum	0.531	mg/kg	B		P	0.115	TJA61 Trace ICP2	80702
7440-02-0	Nickel	3.650	mg/kg	B		P	0.083	TJA61 Trace ICP2	80702
7440-09-7	Potassium	261	mg/kg	B	E	P	2.080	TJA61 Trace ICP2	80702
7782-49-2	Selenium	0.694	mg/kg	B		P	0.264	TJA61 Trace ICP2	80702
7631-86-9	Silica	435	mg/kg		*N	P	1.500	TJA61 Trace ICP2	80902
7440-22-4	Silver	20.5	mg/kg			P	0.114	TJA61 Trace ICP2	80702
7440-23-5	Sodium	134	mg/kg	B		P	3.660	TJA61 Trace ICP2	80702
7440-24-6	Strontium	19.0	mg/kg	B		P	0.015	TJA61 Trace ICP2	80702
7440-28-0	Thallium	0.494	mg/kg	U		P	0.494	TJA61 Trace ICP2	80702
7440-31-5	Tin	0.969	mg/kg	B		P	0.191	TJA61 Trace ICP2	80702
7440-32-6	Titanium	7.610	mg/kg			P	0.024	TJA61 Trace ICP2	80702
7440-61-1	Uranium	3.190	mg/kg	U		P	3.190	TJA61 Trace ICP2	80702
7440-62-2	Vanadium	4.590	mg/kg	B		P	0.079	TJA61 Trace ICP2	80702
7440-66-6	Zinc	209	mg/kg		N	P	0.125	TJA61 Trace ICP2	80702

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

TOTAL METALS
- 1 -
INORGANIC ANALYSIS DATA PACKAGE

SDG No.: 02S0203

Method Type: SW846

Sample ID: 64569002

Client ID: 02S0203-002.002

Contract: KHCO00100

Lab Code: GEL

Case No.: GEL

SAS No.:

Matrix: SOIL

Date Received: 8/1/2002

Level: LOW

% Solids: 100.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7429-90-5	Aluminum	633	mg/kg		*	P	0.601	TJA61 Trace ICP2	80702
7440-36-0	Antimony	0.465	mg/kg	U	N	P	0.465	TJA61 Trace ICP2	80702
7440-38-2	Arsenic	1.640	mg/kg	B		P	0.386	TJA61 Trace ICP2	80702
7440-39-3	Barium	40.2	mg/kg			P	0.018	TJA61 Trace ICP2	80702
7440-41-7	Beryllium	0.168	mg/kg	B		MS	0.006	PE ICPMS3	020805
7440-42-8	Boron	0.381	mg/kg	U		P	0.381	TJA61 Trace ICP2	80702
7440-43-9	Cadmium	0.151	mg/kg	B		MS	0.006	PE ICPMS3	020805
7440-70-2	Calcium	819	mg/kg	B	N	P	1.530	TJA61 Trace ICP2	80702
7440-47-3	Chromium	2.880	mg/kg			P	0.052	TJA61 Trace ICP2	80702
7440-48-4	Cobalt	1.900	mg/kg	B		P	0.056	TJA61 Trace ICP2	80702
7440-50-8	Copper	10.8	mg/kg			P	0.127	TJA61 Trace ICP2	80702
7439-89-6	Iron	1570	mg/kg			P	0.204	TJA61 Trace ICP2	80702
7439-92-1	Lead	6.400	mg/kg	B		P	0.121	TJA61 Trace ICP2	80702
7439-93-2	Lithium	0.577	mg/kg	B		MS	0.006	PE ICPMS3	020805
7439-95-4	Magnesium	197	mg/kg	B		P	0.499	TJA61 Trace ICP2	80702
7439-96-5	Manganese	9.900	mg/kg			P	0.035	TJA61 Trace ICP2	80702
7439-97-6	Mercury	0.009	mg/kg	B		AV	0.003	PE CVAA	080302S1Hg
7439-98-7	Molybdenum	0.585	mg/kg	B		P	0.112	TJA61 Trace ICP2	80702
7440-02-0	Nickel	3.720	mg/kg	B		P	0.081	TJA61 Trace ICP2	80702
7440-09-7	Potassium	249	mg/kg	B	E	P	2.040	TJA61 Trace ICP2	80702
7782-49-2	Selenium	0.796	mg/kg	B		P	0.259	TJA61 Trace ICP2	80702
7631-86-9	Silica	442	mg/kg		*N	P	1.470	TJA61 Trace ICP2	80902
7440-22-4	Silver	17.2	mg/kg			P	0.112	TJA61 Trace ICP2	80702
7440-23-5	Sodium	108	mg/kg	B		P	3.590	TJA61 Trace ICP2	80702
7440-24-6	Strontium	15.9	mg/kg	B		P	0.015	TJA61 Trace ICP2	80702
7440-28-0	Thallium	0.484	mg/kg	U		P	0.484	TJA61 Trace ICP2	80702
7440-31-5	Tin	0.820	mg/kg	B		P	0.187	TJA61 Trace ICP2	80702
7440-32-6	Titanium	9.750	mg/kg			P	0.023	TJA61 Trace ICP2	80702
7440-61-1	Uranium	3.130	mg/kg	U		P	3.130	TJA61 Trace ICP2	80702
7440-62-2	Vanadium	4.960	mg/kg	B		P	0.077	TJA61 Trace ICP2	80702
7440-66-6	Zinc	24.2	mg/kg		N	P	0.123	TJA61 Trace ICP2	80702

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

83

ATTACHMENT D

Data Quality Assessment (DQA) Detail

DATA QUALITY ASSESSMENT (DQA)

VERIFICATION & VALIDATION (V&V) OF RESULTS

V&V of the data confirm that appropriate quality controls are implemented throughout the sampling and analysis process, and that any substandard controls result in qualification or rejection of the data in question. The required quality controls and their implementation are summarized in a tabular, checklist format for each category of data – radiological surveys and chemical analyses (specifically asbestos and beryllium).

DQA criteria and results are provided in a tabular format for each suite of surveys or chemical analyses performed. The radiological survey assessment is provided in Table D-1, asbestos in Table D-2 and beryllium in Table D-3. A data completeness summary for all results is given in Table D-4.

All relevant Quality records supporting this report are maintained in the RISS Characterization Project File. The report will be submitted to the CERCLA Administrative Record for permanent storage within 30 days of approval by the Regulators. All radiological data are organized into Survey Packages, which correlate to unique (MARSSIM) Survey Units. Chemical data are organized by RIN (Report Identification Number) and are traceable to the sample number and corresponding sample location.

Beta/gamma survey designs were not implemented for Building 910 based on the conservatism of the transuranic limits used as DCGLs in the unrestricted release decision process. Survey designs were implemented based on the transuranic limits used as DCGLs in the unrestricted release decision process. All survey results were evaluated against, and were less than the Transuranic DCGL_w (100 dpm/100cm²) and the Uranium DCGL_w (5,000 dpm/100cm²) unrestricted release limits.

Consistent with EPA's G-4 DQO process, the radiological survey design for each survey unit performed per PDS requirements was optimized by checking actual measurement results acquired during pre-demolition surveys against the model output with original estimates. Use of actual sample/survey (result) variances in the MARSSIM DQO model confirms that an adequate number of surveys were acquired.

DQA SUMMARY

In summary, the data presented in this report have been verified and validated relative to the quality requirements and project decisions as stated in the original DQOs. All data are useable based on qualifications stated herein and are considered satisfactory without qualification. All media surveyed and sampled yielded results less than their associated action levels and with acceptable certainties.

Based upon an independent review of the radiological data, it is determined that the original project DQOs satisfied MARSSIM guidance. All facility contamination levels were below applicable DCGL unrestricted release levels confirming Type 2 facility classification. Minimum survey requirements were met, sampling/survey protocol was performed in accordance with applicable RSPs, survey units were properly designed and bounded, and instrument performance and calibration was verified as acceptable. All results meet the PDS unrestricted release criteria.

Chain of Custody was intact; documentation was complete, hold times were acceptable (where applicable,) and packaging integrity/custody seals were maintained throughout the sampling/analysis process. Level 2 Isolation Controls have been posted to prevent the inadvertent introduction of contamination into the facilities. On this basis, building 910 meets the unrestricted release criteria with the confidences stated herein.

Table D-1 V&V of Radiological Results for Building 910

V&V CRITERIA, RADIOLOGICAL SURVEYS		K-H RSP 16.00 Series MARSSIM (NUREG-1575)		COMMENTS
QUALITY REQUIREMENTS		Parameters	Measure	
ACCURACY	Initial calibrations		90% < x < 110%	Multi-point calibration through the measurement range encountered in the field; programmatic records.
	Daily source checks		80% < x < 120%	Performed daily/within range.
	Local area background: Field		typically < 10 dpm	All local area backgrounds were within expected ranges (i.e., no elevated anomalies.)
PRECISION	Field duplicate measurements for TSA		≥ 5% of real survey points	N/A
REPRESENTATIVENESS	MARSSIM methodology: Survey Units 910-A-002 and 910-B-001.		statistical and biased	Random w/ statistical confidence.
	Survey Maps		NA	Random and biased measurement locations controlled/mapped to ± 1m.
	Controlling Documents (Characterization Pkg; RSPs)		qualitative	Refer to the Characterization Package (planning document) for field/sampling procedures (located in Project files); thorough documentation of the planning, sampling/analysis process, and data reduction into formats.
COMPARABILITY	Units of measure		dpm/100cm ²	Use of standardized engineering units in the reporting of measurement results.
COMPLETENESS	Plan vs. Actual surveys Usable results vs. unusable		>95%	See Table D-4 for details.
SENSITIVITY	Detection limits		>95%	
			TSA: ≤ 50 dpm/100cm ² RA: ≤ 10 dpm/100cm ²	PDS MDAs ≤ 50% DCGL _w

87

Table E-2 V&V of Asbestos Results For Building 910

V&V CRITERIA, CHEMICAL ANALYSES		DATA PACKAGE		COMMENTS
ASBESTOS	METHOD: EPA 600/R-93/116	LAB ---->	Reservoirs Environmental, Inc RIN ----> RIN03Z0308	
QUALITY REQUIREMENT		Measure	Frequency	
ACCURACY	Calibrations: Initial/continuing	below detectable amounts	≥ 1	Semi-quantitative, per (microscopic) visual estimation.
PRECISION	Actual Number Sampled LCSD Lab duplicates	all below detectable amounts	≥ 7 samples	Semi-quantitative, per (microscopic) visual estimation.
REPRESENTATIVENESS	COC	Qualitative	NA	Chain-of-Custody intact: completed paperwork, containers w/ custody seals.
	Hold times/preservation	Qualitative	NA	N/A
	Controlling Documents (Plans, Procedures, maps, etc.)	Qualitative	NA	See original Chemical Characterization Package (planning document); for field/sampling procedures (located in project file); thorough documentation of the planning, sampling/analysis process, and data reduction into formats.
COMPARABILITY	Measurement Units	% by bulk volume	NA	Use of standardized engineering units in the reporting of measurement results.
COMPLETENESS	Plan vs. Actual samples Usable results vs. unusable	Qualitative	NA	See Table D-4, final number of samples at Certified Inspector's discretion.
SENSITIVITY	Detection limits	<1% by volume	all measures	N/A

Table D-3 V&V of Beryllium Results for Building 910

V&V CRITERIA, CHEMICAL ANALYSES		DATA PACKAGE	
BERYLLIUM	Prep: NMAM 7300	LAB ---->	Johns Manville, Littleton, Co.
	METHOD: OSHA ID-125G	RIN ---->	RIN03Z0307
QUALITY REQUIREMENTS		Measure	Frequency
ACCURACY	Calibrations Initial	linear calibration	≥1
	Continuing LCS/MS	80%<%R<120%	≥1
	Blanks – lab & field	80%<%R<120%	≥1
	Interference check std (ICP)	<MDL	≥1
	LCSD	NA	NA
PRECISION	Field duplicate	80%<%R<120% (RPD<20%)	≥1
	COC	all results < RL	≥1
REPRESENTATIVENESS	Hold times/preservation	Qualitative	NA
	Controlling Documents (Plans, Procedures, maps, etc.)	Qualitative	NA
	Measurement units	Qualitative	NA
COMPARABILITY	Plan vs. Actual samples	ug/100cm ²	NA
COMPLETENESS	Usable results vs. unusable	>95%	NA
	Detection limits	>95%	NA
SENSITIVITY		MDL of 0.012 ug/100cm ²	all measures
		No qualifications significant enough to change project decisions, i.e. classification of a Type 2 Facility confirmed; all results were below associated action levels.	

Table D-4 Data Completeness Summary For Building 910

ANALYTE	Building/Area /Unit	Sample Number Planned (Real & QC) ^A	Sample Number Taken (Real & QC)	Project Decisions (Conclusions) & Uncertainty	Comments (RIN, Analytical Method, Qualifications, etc.)
Asbestos	B910 (interior)	0 biased	7 biased (interior)	No ACM present, all results were none detect	40 CFR763.86; CCR 1001-10; EPA 600/R-93/116 RIN03Z0308 All PDS asbestos results were none detect. However, ACM identified during the Group A facility RLCR will be removed prior to demolition in accordance with CDPHE Regulation 8. 10CFR850; OSHA ID-125G RIN03Z0307
Beryllium	B910 (interior and exterior)	15 biased	20 biased (14 interior/6 exterior)	No contamination found at any location	No results above the action level (0.2 ug/100cm ²) or investigative level (0.1 ug/100cm ²) Uranium and/or Transuranic DCGL as applicable.
Radiological	Survey Area 2 Survey Unit: 910-A-002 Bldg. 910 (interior)	30 & TSA (15 random/15 biased) and 30 α Smears (15 random/15 biased) 2 QC TSA 5% scan	31 & TSA (16 random/15 biased) and 31 α Smears (16 random/15 biased) 2 QC TSA 5% scan	No contamination at any location; all values below unrestricted release levels	Survey map shows 30 sample locations. An additional sample was taken under the carpet at location 12 (2 samples at this location), therefore, a total of 31 survey results (16 random & 15 biased) are reported in the Radiological Data Summary – PDS. The sand filter tanks have been sealed and will be packaged and removed as low level radioactive waste during demolition in accordance with the PWRE process. The PWRE data can be found in Attachment B, Radiological Data Summary and Survey Maps.

90

Table D-4 Data Completeness Summary For Building 910

ANALYTE	Building/Area /Unit	Sample Number Planned (Real & QC) ^A	Sample Number Taken (Real & QC)	Project Decisions (Conclusions) & Uncertainty	Comments (RIN, Analytical Method, Qualifications, etc.)
Radiological	Survey Area 2 Survey Unit: 910-B-001 Bldg. 910 (exterior)	30 α TSA (15 systematic/15 biased) and 30 α Smears (15 systematic/15 biased) 2 QC TSA 100% scan exterior north wall and 50% scan of remaining exterior surfaces	30 α TSA (15 systematic/15 biased) and 30 α Smears (15 systematic/15 biased) 2 QC TSA 100% scan exterior north wall and 50% scan of remaining exterior surfaces	No contamination at any location; all values below unrestricted release levels	Uranium and/or Transuranic DCGL as applicable. Initial Sample Net Activity for locations 4 and 11 (101.8 dpm/100cm ² and 108.0 dpm/100cm ² respectively) were greater than the Transuranic DCGL _w (100 dpm/100cm ²). In accordance with RSP 16.02, these locations were allowed to decay and re-surveyed. Both re-survey results were less than the Transuranic DCGL _w (100 dpm/100cm ²) and are the values reported in the Radiological Data Summary - PDS. All results are below the unrestricted release levels.

^A Number of asbestos samples required are an estimate only, final number of samples is at the discretion of IH.

9/1/91